


EXIST. CURVE 397 (I-55)
 PI STA. = 397+67.74
 $\Delta = 19^\circ 00' 23''$ (LT)
 $D = 1^\circ 00' 01''$
 $R = 5,727.63'$
 $T = 958.80'$
 $L = 1,899.98'$
 $E = 79.70'$
 $e = 3.34\%$
 $T.R. = 90.0'$
 $S.E. RUN = 150.0'$
 $P.C. STA. = 388+08.94$
 $P.T. STA. = 407+08.92$

NOTE: SEE SE TRANSITION DETAILS SHEETS FOR SE ATTAINMENT ON ALL I-55 MAINLINE CURVES

PAVEMENT MARKING LEGEND

- ① PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 5" (30' SKIP, 10' DASH)
- ② PR URETHANE PAVEMENT MARKING, DOUBLE LINE 5" (SOLID YELLOW)
- ③ PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID YELLOW)
- ④ PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID WHITE)
- ⑤ PR URETHANE PAVEMENT MARKING, LINE 6" (SOLID WHITE)
- ⑥ PR URETHANE PAVEMENT MARKING, LINE 5" (6' SKIP, 2' DASH)
- ⑦ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 8" (SOLID WHITE)
- ⑧ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 12" (SOLID YELLOW)
- ⑨ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 12" (SOLID WHITE)
- ⑩ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 24" (SOLID WHITE)
- ⑪ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LETTERS & SYMBOLS (SOLID WHITE)



FILE NAME =	USER NAME = laughlinr1	DESIGNED - R.A.W.	REVISED -
e:\pwork\pwidot\LAUGHLINR1\0169970\0672C38-RPT-Plan I-55.dgn		DRAWN - R.A.W.	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED - J.S.A.	REVISED -
	PLOT DATE = Oct-28-2009 08:47:20AM	DATE - 7/24/09	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

PLAN SHEET			
STA. 385+00 to 339+00			
SCALE: 1"=50'	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I-55	84-1-2RS4+150RS1	SANGAMON	65	33
CONTRACT NO. 72C38			ILLINOIS FED. AID PROJECT	