

<i>PAVING SCHEDULE</i>			
LOCATION	HMA SURFACE REMOVAL, 1 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED HMA SURFACE COURSE, MIX "D", N70
	(SQ YD)	(TON)	(TON)
41+02.80 TO 43+50.00	1,619	0.62	136
43+50.00 TO 47+50.00	2,668	1.01	224
47+50.00 TO 52+00.00	2,996	1.14	252
52+00.00 TO 56+02.25	2,360	.90	198
SUB TOTALS =	<i>9,643</i>	<i>3.67</i>	<i>810</i>
PINE STREET	79	0.03	6.6
CEDAR STREET	77	0.03	6.5
SPRUCE STREET	157	0.06	13.2
SUB TOTALS =	<i>313</i>	<i>.12</i>	<i>26.3</i>
PARKING LANE			
52+71.00 TO 55+92.67	<i>329</i>	<i>.13</i>	<i>28</i>
OVERALL TOTALS	<i>10,285</i>	<i>3.92</i>	<i>864</i>