



PAVEMENT MARKING SCHEDULE													
LOCATION	DESCRIPTION	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING					WORK ZONE PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING				
			LETTERS & SYMBOLS	LINE 4"	LINE 6"	LINE 12"	LINE 24"		LETTERS & SYMBOLS	LINE 4"	LINE 6"	LINE 12"	LINE 24"
			FOOT	SQ FT	FOOT	FOOT	FOOT		SQ FT	SQ FT	FOOT	FOOT	FOOT
STA 29+03 TO 29+95, LT	SOLID WHITE	16			92			51.3			92		
STA 29+95 TO 30+75, LT	SKIP-DASH WHITE	16			20			15.3			20		
STA 28+25 TO 30+75, RT	SKIP-DASH WHITE	48			70			51.0			70		
STA 29+64 TO 30+75, RT	SOLID WHITE	24			111			63.5			111		
STA 11+31 TO 14+11, LT	SKIP-DASH WHITE	56			70			53.7			70		
STA 11+31 TO 13+09, LT	SOLID WHITE	40			178			102.3			178		
STA 43+09 TO 44+51, RT	SOLID WHITE				142			71.0			142		
STA 28+16, MEDIAN NOSE	SOLID YELLOW - DOUBLE			13				4.3		13			
STA 28+16 TO 30+77, MEDIAN	SOLID YELLOW - DOUBLE	72		1044				372.0		1044			
MEDIAN STRIPES	SOLID YELLOW				80			80.0			80		
STA 30+77, MEDIAN NOSE	SOLID YELLOW - DOUBLE			13				4.3		13			
STA 41+51 TO 43+09, RT	SKIP-DASH WHITE	64			40			41.3			40		
STA 43+69 TO 44+53, MEDIAN	SOLID YELLOW - DOUBLE	32		336				122.7		336			
STA 44+53, MEDIAN NOSE	SOLID YELLOW - DOUBLE			13				4.3		13			
CROSSWALKS	SOLID WHITE				297			148.5			297		
STA 30+77, STOP BAR	SOLID WHITE							84.0					42
STA 31+96, STOP BAR	SOLID WHITE							68.0					34
STA 44+53, STOP BAR	SOLID WHITE							56.0					28
TURN ARROWS	SOLID WHITE		188					188.0	188				
TOTALS		368	188	1419	1020	80	104	1581.5	188	1419	1020	80	104

PAVEMENT & APPURTENANCE REMOVAL SCHEDULE					
LOCATION	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	APPROACH SLAB REMOVAL	MEDIAN REMOVAL	MEDIAN REMOVAL PARTIAL DEPTH
	SQ YD	FOOT	SQ YD	SQ FT	SQ FT
STA 28+23.67 TO W. ABUTMENT, RT		180			
STA 29+03.00 TO W. ABUTMENT, LT		122			
STA 29+03.00 TO W. ABUTMENT, CL				450	
STA 29+03.00 TO EX W. APPROACH SLAB, LT & RT	442.2				
EX W. APPROACH SLAB			157		
EX E. APPROACH SLAB			232		
E. ABUTMENT TO STA 31+98.04, LT		84			
EX E. APPROACH SLAB TO STA 31+72.00, LT & RT	46.2				
STA 43+65.1 TO E. ABUTMENT, LT		124			
STA 44+46.1 TO 44+79.5, LT	36.6				
STA 28+16.5 TO 29+03.00, CL					346
STA 43+67.6 TO 44+52.00, CL					338
TOTALS	525.0	510	389	450	684

PROTECTIVE COAT SCHEDULE	
LOCATION	PROTECTIVE COAT
	SQ YD
PCC PAVEMENT 9"	100
PCC PAVEMENT CONNECTOR	69
CRC PAVEMENT 9"	561
CONC CURB & GUTTER, TYPE B-6.24	94
SW ANCHOR SLAB	35
SE ANCHOR SLAB	86
PCC DRIVEWAY	188
PCC SIDEWALK	117
BRIDGE DECK AND APPROACH PAVEMENTS	1518
TOTAL	2768

SURVEY MARKERS SCHEDULE	
LOCATION	PERMANENT SURVEY MARKERS, TYPE I
PT STA 28+70.91	1
STA 31+38.45 = STA 45+13.34, CL	1
TOTAL	2

CHAIN LINK FENCE SCHEDULE		
LOCATION	CHAIN LINK FENCE, 6'	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED
	FOOT	FOOT
SE RETAINING WALL	18	
NE RETAINING WALL		17
SW RETAINING WALL		6
NW RETAINING WALL		18
TOTALS	18	41