

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODES					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SN 058-0093	SN 058-0094	SN 058-0095	SN 058-0096	SN 058-0097	ROADWAY
				SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	I000
20400800	FURNISHED EXCAVATION	CU YD	661	165.3	165.3	165.3	165.1		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	152			152			
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5	0.125	0.125	0.125	0.125		
35650500	BASE COURSE WIDENING 10"	SQ YD	174					174	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	129			129			
44000100	PAVEMENT REMOVAL	SQ YD	67.6			67.6			
44000700	APPROACH SLAB REMOVAL	SQ YD	162			162			
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	7400	1740	1749	1506	1506	899	
44004250	PAVED SHOULDER REMOVAL	SQ YD	99			99			
50102400	CONCRETE REMOVAL	CU YD	137.7	11.6	11.6	49.2	53.3	12	
50157300	PROTECTIVE SHIELD	SQ YD	3284			1124	1124	1036	
50200100	STRUCTURE EXCAVATION	CU YD	152			152			
50300100	FLOOR DRAINS	EACH	156	30	30	40	40	16	
50300225	CONCRETE STRUCTURES	CU YD	19.3			19.3			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	211.5	13.8	14.1	110.9	59.4	13.3	
50300260	BRIDGE DECK GROOVING	SQ YD	7400	1740	1749	1506	1506	899	
50300300	PROTECTIVE COAT	SQ YD	7603	1740	1749	1709	1506	899	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	10030	2355	2355	1710	1710	1900	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	56	12	12	12	12	8	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	42100	3490	3530	25030	7040	3010	
50800515	BAR SPLICERS	EACH	224	28	28	72	72	24	
51500200	RELOCATING NAME PLATES	EACH	2			1	1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	658	96	96	192	192	82	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12	6	6				
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	44	6	6	12	12	8	
52100520	ANCHOR BOLTS, 1"	EACH	96	24	24	24	24		
52100540	ANCHOR BOLTS, 1 1/2"	EACH	16					16	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	70			70			
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	142						142
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	1191.5						1191.5
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	72			72			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1350	187.5	387.5	387.5	387.5		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	7	2	1	2	2		
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	7	2	1	2	2		
* 63100215	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	2	1	1				

*Specialty Items

FILE NAME =	USER NAME = swartzw	DESIGNED - JLD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cd:\pw_work\pwsidot\swartzw\dms37771\shsbq_74343.dgn		DRAWN - RWS	REVISED -					72	66B,HVB,HB-1BR	MACON	83	4
	PLOT SCALE = 100.0000' / IN.	CHECKED - WES	REVISED -		SCALE: NA	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 74343	
	PLOT DATE = 10/7/2009	DATE - 10-07	REVISED -									