SUMMARY OF QUANTITIES (Cont'd)

	CODE NO	ITEM	UNIT	90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODES					
					SN 058-0093	SN 058-0094	SN 058-0095	SN 058-0096	SN 058-0097	ROADWAY
					SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	1000
	63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	1368.5	220.7	395.1	376.5	376.2		
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1.2	1.2	1.2	1.2	1.2	
	67100100	MOBILIZATION	L SUM	1	0.2	0.2	0.2	0.2	0.2	
	70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1					1	
	70101220	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411 (SPECIAL)	EACH	4	1	1	1	1		
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2					2	
	70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2					2	
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	2475	625	625	637.5	587.5		
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2475	625	625	637.5	587.5		
*	78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	3435	826	847	883	879		
*	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	429	103	106	110	110		
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	43	10	11	11	11		
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	54	15	23	8	8		
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	1	2	2	2		
	X0301271	REMOVE EXISTING UNDERDRAINS	FOOT	1191.5						1191.5
	X0321468	PLUG EXISTING DECK DRAINS	EACH	174	33	33	46	46	16	
	X0323644	PAVEMENT MARKING GROOVING	FOOT	3864	929	953	993	989		
	X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	70			70			
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	888	121	167	266	193	141	
	X0325983	BRIDGE DECK FLY ASH OR GGBF SLAG CONCRETE OVERLAY, 2 1/4"	SQ YD	899					899	
	X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	142						142
	X7010820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	L SUM	1	0.25	0.25	0.25	0.25		
	X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	7	7	7	7		
	XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	6501	1740	1749	1506	1506		
	Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	7400	1740	1749	1506	1506	899	
	Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	38	7	7	10	10	4	
	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	117	10	18	26	32	31	
	Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	1	1	1	1		
	Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	1	1	1	1		
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1			0.5	0.5		
⊙	Z0076600	TRAINEES	HOUR	500	100	100	100	100	100	

*Specialty Items
⊙ Y080

FILE NAME = c:\pw_work\pwidot\swartzrw\dms37771\shtsbq_74343.dgn	USER NAME = swartzrw	DESIGNED - JLD	REVISED -
		DRAWN - RWS	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED - WES	REVISED -
	PLOT DATE = 10/7/2009	DATE - 10-07	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA | SHEET NO. 2 OF 2 SHEETS | STA. | TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	66(B,HVB,HB-1)BR	MACON	83	5
		CONTRACT NO. 74343		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT