

PIPE UNDERDRAIN & HEADWALL SCHEDULE

(Length of Pipe Underdrain Removal and Installation of new Pipe underdrain is from edge of bituminous shoulder to headwall)

Location	Station (Headwalls)	Pipe U.D. (Foot)
Right median	703+70	9.0
Left median	703+70	9.0
Right shoulder	704+70	8.5
Right median	708+80	9.0
Left median	708+80	9.0
Left median	713+50	9.0
Right median	714+00	8.5
Right median	718+50	11.5
Left median	718+50	9.0
Left median	724+20	9.0
Right median	728+25	9.0
Left shoulder	728+40	7.0
Left median	729+35	9.0
Left median	734+40	9.0
Left shoulder	734+50	7.0
Right shoulder	735+00	7.0
Right median	735+00	9.0
Left shoulder	739+50	11.0
Right median	740+10	9.0
Right shoulder	740+75	8.0
Left median	741+05	9.0
Left shoulder	744+50	10.5
Right median	745+15	9.0
Left median	746+20	9.0
Right shoulder	747+35	8.0
Right median	750+35	9.0
Left median	751+20	9.0
Right shoulder	753+70	6.5
Left shoulder	755+00	16.5
Right median	755+40	9.0
Left median	756+15	9.0
Right shoulder	759+00	7.0
Right median	760+50	9.0
Right median	761+15	9.0
Right shoulder	764+30	10.5
Left shoulder	765+00	7.0
Right median	765+50	9.0
Left median	766+15	9.0
Right shoulder	769+75	10.5
Left shoulder	770+50	12.0
Left median	771+50	9.0
Right median	772+50	9.0
Right shoulder	775+40	7.5
Left median	776+25	9.0
Right median	777+75	9.0
Right shoulder	779+40	7.0
Right median	781+10	9.0
Left median	781+45	9.0
Left shoulder	781+45	7.0
Column Total		439.5

Right median	786+25	9.0
Right shoulder	786+30	12.0
Left shoulder	786+20	7.0
Left median	786+50	9.0
Right median	791+30	9.0
Left median	791+45	8.5
Left shoulder	791+45	7.0
Right shoulder	791+50	9.0
Left shoulder	805+25	7.0
Left median	805+50	9.0
Right shoulder	805+60	7.5
Right median	805+60	9.0
Right shoulder	808+50	7.0
Right median	808+50	9.0
Left median	810+70	8.5
Left shoulder	810+70	6.5
Right shoulder	813+40	7.0
Right median	813+40	9.0
Left shoulder	816+60	6.5
Left median	816+65	9.0
Left shoulder	818+85	7.0
Left median	818+90	9.0
Right median	819+00	9.0
Right shoulder	819+00	6.5
Right median	823+50	9.0
Right shoulder	823+50	7.0
Left shoulder	823+95	7.0
Left median	824+00	9.0
Right shoulder	828+60	7.0
Right median	828+75	9.0
Left shoulder	829+15	7.0
Left median	829+25	8.5
Right shoulder	833+70	7.0
Right median	833+75	9.0
Left shoulder	834+30	7.0
Left median	834+50	8.5
Right shoulder	837+40	7.5
Right median	838+75	9.0
Left shoulder	839+15	7.5
Left median	839+20	8.5
Right shoulder	842+30	7.0
Right median	843+75	9.0
Left shoulder	844+25	7.5
Left median	845+25	8.5
Right shoulder	846+90	6.0
Right median	848+75	9.0
Left median	849+40	8.5
Left shoulder	849+40	7.5
Right shoulder	851+95	6.5
Left median	858+00	8.5
Left shoulder	858+00	7.5
Column Total		410.0

Right median	859+00	9.0
Right shoulder	861+70	7.0
Left median	863+20	8.0
Left shoulder	863+20	8.0
Right median	864+00	9.0
Right shoulder	867+25	7.0
Left median	867+50	9.0
Left shoulder	867+50	8.0
Right median	869+00	9.0
Left median	871+75	9.0
Left shoulder	871+75	8.0
Right shoulder	872+30	7.0
Right median	874+20	9.0
Left median	876+00	9.0
Left shoulder	876+00	8.0
Right shoulder	877+50	6.0
Right median	879+25	9.0
Left median	880+00	9.0
Left shoulder	880+00	7.5
Right shoulder	883+40	7.5
Left median	883+80	9.0
Left shoulder	883+80	8.0
Right median	884+20	9.0
Left median	887+50	9.0
Left shoulder	887+50	7.5
Right shoulder	887+60	7.5
Right median	889+40	9.0
Left median	891+00	9.0
Right shoulder	892+50	7.0
Left shoulder	892+50	7.5
Right median	894+50	8.5
Right shoulder	897+50	7.0
Left shoulder	897+70	7.0
Right median	899+50	8.5
Right shoulder	902+50	7.0
Left median	902+50	8.5
Left shoulder	902+50	8.0
Right median	905+00	8.5
Right shoulder	907+50	7.5
Left median	907+50	9.0
Left shoulder	907+50	8.0
Right median	910+00	9.0
Column Total		342.0
Project Totals	*142	**1191.5

THESE TOTALS ARE FOR THE FOLLOWING PAY ITEMS:
 *CONCRETE HEADWALLS FOR PIPE DRAINS
 CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL
 **PIPE UNDERDRAINS 4" (SPECIAL)
 REMOVE EXISTING UNDERDRAINS

BRIDGE APPROACH PAVEMENT REMOVAL

LOCATION				LENGTH FEET	WIDTH FEET	AREA SQ YD
RT.	801+86.00	TO	802+26.00	40.0	36.5	162.2
PROJECT TOTAL						162.2

PAVED SHOULDER REMOVAL

LOCATION				LENGTH FEET	WIDTH FEET	AREA SQ YD
RT. MEDIAN						
	801+51.52	TO	801+58.42	6.9	6.0	2.3
	801+58.42	TO	802+33.68	75.3	6.0	50.2
RT. SHOULDER						
	801+86.00	TO	801+97.68	11.7	10.0	6.5
	801+97.68	TO	802+33.68	36.0	10.0	40.0
PROJECT TOTAL						99.0

PAVEMENT REMOVAL

LOCATION				LENGTH FEET	WIDTH FEET	AREA SQ YD
RT. MED	801+72.20	TO	802+26.00	35.3	24.0	47.1
RT. SHLD	802+26.00	TO	802+33.68	7.7	24.0	20.5
PROJECT TOTAL						67.6