

PAVEMENT MARKING SCHEDULE

STATION	THERMOPLASTIC PAVEMENT MARKING LINE-4" (FOOT)		POLYUREA PAVEMENT MARKING LINE-4" (FOOT)		SHORT TERM PAVEMENT MARKING (FOOT)	RAISED REFLECTIVE PAVEMENT MARKERS (EACH)	RAISED REFLECTIVE PAVT. MRKS. (BRIDGE) (EACH)	RAISED REFLECTIVE PAVT. MRK. REMOVAL (EACH)	PAVEMENT MARKING REMOVAL (SQ FT)	WORK ZONE PAVEMENT MRK. REM. (SQ FT)
	SOLID WHITE	SKIP-DASH YELLOW	SOLID WHITE	SKIP-DASH YELLOW						
36+79.00 TO 38+00.00	242	30			36.3	2		2	60.5	92.8
38+00.00 TO 39+00.05	200	25			30.0	1		1	50.0	76.7
39+00.05 TO 40+79.55			360	45	53.9		2	2	89.8	18.0
40+79.55 TO 42+00.00	240	30			36.1	2		2	60.2	92.3
42+00.00 TO 43+42.00	284	36			42.6	2		2	71.0	108.9
SUBTOTAL	968	121	360	45	198.9	7	2	9	331.5	388.6
TOTAL		1088		405	199.0	7	2	9	332.0	389.0

SUMMIT AVENUE PAVING SCHEDULE

STATIONING	BIT. MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	HMA SURF. CSE MIX "C", N70 (TON)	HMA BASE COURSE WIDENING-10" (SQ YD)	PAVEMENT REMOVAL (SQ YD)	HMA SURF. REM. BUTT JOINT (SQ YD)	EARTH EXCAVATION WIDENING (CUY)
36+79.00 TO 38+00.00	0.00	0.00	0.0	107.6	0.0	0.0	10.0
38+00.00 TO 39+36.05	0.09	0.43	24.5	104.9	88.0	73.5	10.0
40+43.55 TO 42+00.00	0.11	0.52	29.5	123.3	88.0	73.5	11.0
42+00.00 TO 43+42.00	0.00	0.00	0.0	126.2	0.0	0.0	12.0
TOTAL	0.2	1.0	54.0	462.0	176.0	147.0	43.0

