

..\DBCONN-03-BORDER.DGN, ..\DBCONN-03-SCHEDULE.DGN, ..\DBCONN-99-MOTIF.DGN, ..\DBCONN-03-SCHEDULE.DGN, ..\DBCONN-03-SCHEDULE.DGN
 BONDHJJD C:\C-WORKSPACE\BONDHJJD\12-09-2009\10101002 CONTRACTS\CONNSHEETS CONTRACT 03\DBCONN-03-SHT-SCHEDULE.DGN

PAVEMENT MARKING SCHEDULE																		
STATION	TO	STATION	ROADWAY	TYPE	TEMPORARY PAVT MARKING LETTERS & SYMBOLS SQ FT	TEMPORARY PAVT MARKING LINE 4" FOOT	TEMPORARY PAVT MARKING LINE 6" FOOT	TEMPORARY PAVT MARKING LINE 8" FOOT	TEMPORARY PAVT MARKING LINE 12" FOOT	TEMPORARY PAVT MARKING LINE 24" FOOT	POLYUREA PAVT MARKING TYPE I LETTERS & SYMBOLS SQ FT	POLYUREA PAVT MARKING TYPE I LINE 4" FOOT	POLYUREA PAVT MARKING TYPE I LINE 6" FOOT	POLYUREA PAVT MARKING TYPE I LINE 8" FOOT	POLYUREA PAVT MARKING TYPE I LINE 12" FOOT	POLYUREA PAVT MARKING TYPE I LINE 24" FOOT	RAISED REFLECTIVE PAVT MARKERS EACH	PAVEMENT MARKING REMOVAL SF FT
49+30.36	TO	60+00.00	EXCHANGE AVE.			3,171	87					3,171	87					
60+00.00	TO	70+69.66	EXCHANGE AVE.			3,740				50		3,740				50		
5+40.50	TO	18+00.00	N. FIRST STREET			7,216			101			7,216			101			
19+92.72	TO	20+23.72	PACKERS AVE.			70				25		70				25		
69+46.87	TO	70+00.00	MAIN STREET							25						25		
18+00.00	TO	20+94.66	N. FIRST STREET			2,095				70		2,095				70		
		18+58.53	N. FIRST STREET	LT ARROW	15.6						15.6							
		19+08.83	N. FIRST STREET	LT ARROW	15.6						15.6							
		19+58.83	N. FIRST STREET	LT ARROW	15.6						15.6							
83+21.53	TO	86+01.41	ST. CLAIR AVE.			845		920	119			845		510	119		14	806
		83+50.05	ST. CLAIR AVE.	LT ARROW	15.6						15.6							
		84+50.00	ST. CLAIR AVE.	RT/THRU ARROW	31.2													31.2
		84+50.56	ST. CLAIR AVE.	LT ARROW	15.6						15.6							
		85+00.00	ST. CLAIR AVE.	RT/THRU ARROW	31.2													31.2
		85+52.15	ST. CLAIR AVE.	LT ARROW	15.6						15.6							
TOTAL					156	17,137	87	920	220	170	94	17,137	87	510	220	170	14	868

CONCRETE CURB, TYPE B		TOTAL 457 FOOT
DRIVEWAY CENTERLINE		
50+10.33	53	
50+77.93	76	
56+79.21	105	
59+76.47	76	
60+50.09	89	
SIDEWALK		
58+26.79	29	
58+36.79	29	

FILE NAME =	USER NAME = *USER*	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION I-70 CONNECTION	SCHEDULE OF QUANTITIES 6				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#		DRAWN - JB	REVISED -						9153	82-1K	ST. CLAIR	107	15
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT SCALE = *SCALE*	CHECKED - ACL	REVISED -		SCALE: N.T.S.	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 76C40		
	PLOT DATE = *DATE*	DATE - 10/09/09	REVISED -		FED. ROAD DIST. NO.				ILLINOIS FED. AID PROJECT				