

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 100% FED	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY I000-2A	SIGN STRUCTURES Y002-1C	I-70 OVER CANTEEN CREEK 060-0010 EB 060-0011 WB X071-2A	I-70 OVER IL 157 060-0012 EB 060-0013 WB X271-2A	I-70 OVER BELT LINE RD 060-0014 EB 060-0015 WB X241-2A	I-255 RAMP OVER I-70 060-0205 X271-2A	I-255 RAMP OVER I-70 060-0211 X271-2A
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	29	29						
44201003	CLASS B PATCHES, TYPE I, 13 INCH	SQ YD	8	8						
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	250	250						
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	48	48						
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	27	27						
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	21	21						
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	72	72						
44201296	DEFORMED BARS - EXPANSION JOINT	EACH	60	60						
44213100	PAVEMENT FABRIC	SQ YD	75	75						
44213200	SAW CUTS	FOOT	1822	1822						
45200300	JOINT OR CRACK FILLING	POUND	30					30		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3422	3422						
48203045	HOT-MIX ASPHALT SHOULDERS, 12"	SQ YD	58	58						
48203100	HOT-MIX ASPHALT SHOULDERS	TON	8286	8286						
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	13789	13789						
48301000	PROTECTIVE COAT	SQ YD	13789	13789						
50102400	CONCRETE REMOVAL	CU YD	250.3				90.5	89.9	23.5	46.4
50200100	STRUCTURE EXCAVATION	CU YD	28				15	13		
50300225	CONCRETE STRUCTURES	CU YD	38			5	12.6	20.4		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	246.1				88.9	87.1	23.5	46.6
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	90827			7100	17610	64530	175	1412
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	96			20	64	12		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	39390			730	16390	9060	4900	8310
50800515	BAR SPLICERS	EACH	177				52	40	48	37
52000110	PREFORMED JOINT STRIP SEAL	FOOT	999.5				357	473.5	99	70
52000320	NEOPRENE EXPANSION JOINT 2"	FOOT	411			306				105
52000325	NEOPRENE EXPANSION JOINT 2 1/2"	FOOT	306			306				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	64			20	32	12		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	32				32			

FILE NAME =	USER NAME = keplarcl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\FWIDOT\KEPLARCL\ad8133026\ad8133026.sht-plan.dgn	6c56-sht-plan.dgn	DRAWN -	REVISED -			70	60-(5,6,7)RS, 60-(6,7)BR	MADISON	185	5
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			SCALE: _____		SHEET NO. OF SHEETS		TO STA. _____
	PLOT DATE = 12/14/2009	DATE -	REVISED -			CONTRACT NO. 76C56				
						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				