

PAVEMENT MARKING SCHEDULE

LOCATION	DIRECTION	SIDE	THERMOPLASTIC PAVEMENT MARKING					LETTERS AND SYMBOLS WHITE	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B		RAISED REFLECTIVE PAVEMENT MARKER			SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING			DELINEATORS	DELINEATOR REMOVAL
			LINE 4" YELLOW	LINE 4" WHITE	LINE 6" YELLOW	LINE 6" WHITE	LINE 8" WHITE		INLAID - LINE 6" WHITE	LINE 6" WHITE	MARKER REMOVAL	MARKER	MARKER (BRIDGE)		LINE 4"	LINE 6"	LINE 8"		
			FOOT	FOOT	FOOT	FOOT	FOOT		SQ FT	FOOT	FOOT	EACH	EACH		EACH	FOOT	FOOT		
I-55/70																			
371+00.00 TO 374+49.00	WB	LT																1	1
371+00.00 TO 374+73.54	WB	LT											48		1122				
371+00.00 TO 375+30.00	WB								220		20	20	176		440				
371+00.00 TO 375+60.45	WB	RT											60		1383				
371+00.00 TO 376+57.02	EB	LT											72		1674				
371+00.00 TO 377+15.00	EB								300		32	32	96		600				
371+00.00 TO 377+43.93	EB	RT											84		1932				
371+00.00 TO 377+68.00	EB	RT															2	2	
371+00.00 TO 389+54.69	WB	LT					1857												
371+00.00 TO 565+00.00	WB	RT																	
371+00.00 TO 565+00.00	EB	LT																	
371+00.00 TO 393+58.00	EB	RT																	
374+73.54 TO 377+61.54	WB	LT																	
375+30.00 TO 378+20.00	WB										140	16	12		288				
375+60.45 TO 378+48.45	WB	RT											56		140				
376+57.02 TO 379+45.02	EB	LT											12		288				
377+15.00 TO 380+03.00	EB										140	16	12		288				
377+37.00 TO 389+53.00	WB	LT											56		140			12	12
377+43.93 TO 380+31.93	EB	RT																	
377+61.54 TO 389+54.69	WB	LT																	
378+20.00 TO 405+00.00	WB																		
378+20.00 TO 513+07.00	WB																		
378+48.45 TO 512+88.03	WB	RT																	
379+45.02 TO 512+23.32	EB	LT																	
380+03.00 TO 483+50.00	EB																		
380+03.00 TO 512+04.00	EB																		
380+31.93 TO 393+58.00	EB	RT																	
380+56.00 TO 387+05.00	EB	RT																2	2
384+12.00																			
385+25.08 TO 389+70.37	WB	GORE						892											
387+04.87 TO 391+33.21	EB	AUX						87											
387+05.00 TO 393+29.00	EB	RT																	
389+20.00 TO 399+99.00	WB	LT																	
389+70.37 TO 433+62.46	WB	LT					4394											6	6
390+14.00																			
391+33.21 TO 393+62.17	EB	GORE																	
393+12.00 TO 424+55.00	EB	RT																	
393+62.17 TO 424+55.52	EB	RT					3094											3	3
397+13.00																			
399+75.22 TO 417+00.29	EB	AUX																	
399+99.00 TO 433+62.00	WB	LT																	
404+16.00																			
405+00.00 TO 421+63.00	WB																		
417+00.29 TO 424+67.57	EB	GORE																	
419+00.00																			
421+63.00 TO 495+79.00	WB																		
422+00.00																			
424+17.00 TO 449+00.00	EB	RT																	
424+67.57 TO 448+50.34	EB	RT																	
427+82.09 TO 430+79.27	WB	GORE																	
429+00.00																			
430+79.27 TO 433+76.19	WB	GORE																	
433+26.00 TO 446+98.00	WB	LT																	
433+76.19 TO 459+56.70	WB	LT																	
446+98.00 TO 459+57.00	WB	LT																	
448+50.34 TO 450+24.53	EB	GORE																	
448+66.00 TO 461+22.00	EB	RT																	
448+64.67 TO 471+74.40	EB	RT																	
450+02.50																			
450+24.53 TO 453+23.90	EB	GORE																	
454+98.72 TO 457+98.83	WB	GORE																	
456+00.00																			
457+98.83 TO 459+71.23	WB	GORE																	
459+22.00 TO 477+90.00	WB	LT																	
459+72.32 TO 477+40.09	WB	LT																	
461+22.00 TO 472+25.00	EB	RT																	
471+74.41 TO 478+29.09	EB	GORE																	
471+84.86 TO 503+43.13	EB	RT																	
477+40.09 TO 481+65.49	WB	GORE																	

LAST SAVED = 9/15/2009
 PEN TABLE = VB.tbl
 PLOT DRIVER = TR-Xerox6204-1-1-File.plt

FILE NAME =
 1:\08090\work_order_3\cad\1\plans\087655-Sht-Schedule.dgn

USER NAME = sdonahue
 DESIGNED -
 DRAWN -
 CHECKED -
 PLOT DATE = 9/16/2009 8:51:44 PM

REVISOR -
 REVISIONS -
 REVISIONS -
 REVISIONS -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**



**SCHEDULES OF QUANTITIES
 PAVEMENT MARKING**

SCALE: NONE SHEET NO. 8 OF 12 SHEETS STA. TO STA.

F.A.I. RTE. 70	SECTION 60-(5,6,7)RS, 60-(6,7)BR	COUNTY MADISON	TOTAL SHEETS 185	SHEET NO. 20
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		
CONTRACT NO. 76C56				