

**PAVEMENT MARKING SCHEDULE**

LOCATION	DIRECTION	SIDE	THERMOPLASTIC PAVEMENT MARKING							PREFORMED PLASTIC PAVEMENT MARKING, TYPE B		RAISED REFLECTIVE PAVEMENT MARKER			SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING			DELINEATORS	DELINEATOR REMOVAL
			LINE 4" YELLOW	LINE 4" WHITE	LINE 6" YELLOW	LINE 6" WHITE	LINE 8" WHITE	LETTERS AND SYMBOLS WHITE	INLAID - LINE 6" WHITE	LINE 6" WHITE	MARKER REMOVAL	MARKER	MARKER (BRIDGE)	LINE 4"		LINE 6"	LINE 8"			
			FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	EACH	EACH	EACH	FOOT		FOOT	FOOT	EACH		
477+51.36 TO 478+02.00	WB	LT				2122		2						84			2122		21	21
478+29.09 TO 483+50.00	EB	GORE					50					410	80	80						150
483+50.37 TO 495+00.00	EB	AUX					330	6												990
495+79.00 TO 495+79.19	WB	GORE					633	2		430		44	44						1899	
498+47.00 TO 499+86.00	WB	LT				1079		2						44		1079		3	3	
499+86.00 TO 499+85.96	EB	GORE					523	2		200		20	20						1569	
502+00.00 TO 503+00.00								2												
503+13.00 TO 503+61.95	EB	RT				241		2						36		723		1	1	
506+00.89 TO 506+20.74	EB	GORE					370	4												
506+20.74 TO 506+93.00	EB	RT				5893		2						72		1635	1110			
507+83.00 TO 509+25.00	EB							2		220		20	20						5	5
509+82.96 TO 509+90.13	WB	GORE					525										1575			
509+90.13 TO 510+40.00	WB	LT				5513														
510+40.00 TO 511+65.29	WB	RT												16		318		14	14	
511+65.29 TO 512+04.00	EB	RT										160	16	64	160					
512+23.32 TO 512+88.03	EB	LT												16	318					
512+88.03 TO 513+07.00	WB	RT										160	16	16	318					
513+07.00 TO 513+49.88	WB	LT												64	160					
513+49.88 TO 514+75.00	WB	RT												16	318					
514+75.00 TO 514+82.79	EB	RT												348	8610				13	13
514+82.79 TO 515+21.00	EB							2		400		20	20							
515+21.00 TO 515+40.82	EB	LT												728	1820					
515+40.82 TO 516+05.29	EB	RT												336	8358					
516+05.29 TO 516+25.00	WB	RT												324	8037					
516+25.00 TO 516+63.82	WB	LT								660		66	66	528	1320					
516+63.82 TO 516+64.00	WB							2						312	7785					
516+64.00 TO 519+24.00								2												
519+24.00 TO 520+42.00								2												
520+42.00 TO 520+44.00								2												
520+44.00 TO 523+06.00	EB									510		50	50							
523+06.00 TO 524+10.00	WB	LT						2											5	5
524+10.00 TO 524+24.00	WB	LT						2												
524+24.00 TO 528+15.00	EB	RT						2											4	4
528+15.00 TO 531+83.00								2												
531+83.00 TO 531+89.00								2												
531+89.00 TO 531+94.00								2												
531+94.00 TO 532+64.00								2												
532+64.00 TO 535+70.00								2												
535+70.00 TO 535+82.00								2												
535+82.00 TO 535+95.00								2												
535+95.00 TO 537+32.00								2												
537+32.00 TO 538+95.00								2												
538+95.00 TO 539+00.00								2												
539+00.00 TO 539+38.00								2												
539+38.00 TO 542+00.00								2												
542+00.00 TO 542+58.10	WB	LT						2						12	259					
542+58.10 TO 542+71.00	WB	LT						2				60	6							
542+71.00 TO 542+83.84	WB	RT											6	24	60					
542+83.84 TO 543+26.73	WB	LT												12	259					
543+26.73 TO 545+85.14	EB	LT												12	259					

LAST SAVED = 9/15/2009  
 PEN TABLE = VB.tbl  
 PLOT DRIVER = TR-Xerox6204-TopFlt.plt

FILE NAME =  
 USER NAME = sdomahue  
 DESIGNED -  
 DRAWN -  
 PLOT SCALE = 50.0023' / IN.  
 PLOT DATE = 9/16/2009 8:51:45 PM

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**HORNER &  
 SHIFRIN, INC.**  
 ENGINEERS  
 SCALE: NONE

**SCHEDULES OF QUANTITIES  
 PAVEMENT MARKING**

SHEET NO. 9 OF 12 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-(5,6,7)RS, 60-(6,7)BR	MADISON	185	21
CONTRACT NO. 76C56				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				