

PAVEMENT MARKING SCHEDULE																				
LOCATION	DIRECTION	SIDE	THERMOPLASTIC PAVEMENT MARKING						PREFORMED PLASTIC PAVEMENT MARKING, TYPE B		RAISED REFLECTIVE PAVEMENT MARKER			SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING			DELINEATORS	DELINEATOR REMOVAL	
			LINE 4" YELLOW	LINE 4" WHITE	LINE 6" YELLOW	LINE 6" WHITE	LINE 8" WHITE	LETTERS AND SYMBOLS WHITE	INLAID - LINE 6" WHITE	LINE 6" WHITE	MARKER REMOVAL	MARKER	MARKER (BRIDGE)		LINE 4"	LINE 6"	LINE 8"			
			FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	EACH	EACH	EACH		FOOT	FOOT	FOOT			FOOT
3+57.54 TO 22+55.02	RAMP 3	LT	1952									240	5856							
3+57.54 TO 22+55.02	RAMP 3	RT		1898								228	5694							
4+55.00	RAMP 3								2											
5+00.00	RAMP 3								2											
8+59.00	RAMP 3								2											
9+88.00 TO 22+56.00	RAMP 3	LT																	23	23
10+88.00	RAMP 3								4											
13+46.00	RAMP 3								2											
13+62.00	RAMP 3								2											
18+16.00	RAMP 3								2											
18+50.00	RAMP 3								2											
		TOTAL	5501	5402	41101	43625	8561	152	16430	1990	1878	1848	76	16545	31064	203238	25683	368	368	

MANHOLES AND INLETS ADJUSTMENT SCHEDULE				
LOCATION	DIRECTION	SIDE	MANHOLES TO BE ADJUSTED	INLETS TO BE ADJUSTED
			EACH	EACH
I-55/70				
ROADWAY "A"	WB	GORE	1	
I-255 RAMP 2	EB	GORE		1
I-255 RAMP 1	WB	GORE		1
561+00	WB	RT SHLD		1
TOTAL			1	3

FURNISHED EXCAVATION SCHEDULE	
LOCATION	FURNISHED EXCAVATION
	CU YD
I-55/70	
ESTIMATED QUANTITY FOR EMBANKMENT TO BRING EXISTING FOUNDATIONS INTO COMPLIANCE WITH THE BDE MANUAL SECTION 50-3.04(C)	
	100
TOTAL	100

SIGN PANEL SCHEDULE			
LOCATION	SIGN STRUCTURE NUMBER	DESCRIPTION	SIGN PANEL TYPE 3
			SQ FT
I-55/70			
	8S0601055L011.2	EXIT 10	168.75
	8S0601055L011.2	EXIT 11	235.75
	8S060055R008.8	EXIT 9	106.25
	8S0601055L011.4	EXIT 10	175.00
	8S0601055L011.4	EXIT 11	229.50
	8S0601055L011.4	STATE POLICE	237.50
	8S0601055R010.9	CHICAGO	300.00
	8S0601055R010.9	EXIT 11	221.00
TOTAL			1673.75

WOVEN WIRE FENCE SCHEDULE				
LOCATION	DESCRIPTION	DIRECTION	WOVEN WIRE FENCE, 4'	WOVEN WIRE GATES, 4' X 4' SINGLE
			FOOT	EACH
I-55/70				
	419+52	EB	400	
	469+70	WB	500	
	480+25	WB	300	
	NEAR IDOT OFFICE	WB		1
TOTAL			1200	1

LAST SAVED = 9/15/2009  
PEN TABLE = V8.tbl  
PLOT DRIVER = TR-Xerox6204-TopFile.plt

FILE NAME =	USER NAME = sdonehue	DESIGNED -	REVISED -
\\08090\work_order\3\cad\plans\0876256-Sht-Schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0023 // IN.		CHECKED -	REVISED -
PLOT DATE = 9/16/2009 8:51:46 PM		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION



SCHEDULES OF QUANTITIES  
PAVEMENT MARKING, INLET ADJUSTMENT, EARTH EXCAVATION

SCALE: NONE SHEET NO. 11 OF 12 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-(5,6,7)RS, 60-(6,7)BR	MADISON	185	23
CONTRACT NO. 76C56				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				