

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SALINE CO.	SALINE CO.	SALINE CO.
				ROADWAY URBAN 80% FED 20% STATE	PARKING LANES URBAN 80% FED 20% CITY	ROADWAY RURAL 80% FED 20% STATE
CONSTRUCTION TYPE CODE				1000	1000	1000
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1,222	1,222		
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	188	188		
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	5,340	2,415	155	2,770
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	219	219		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	45,141	12,239	1,725	31,177
44000173	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	SQ YD	64	64		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	253	253		
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	75	7		68
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	803	241		562
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	157	39		118
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1,243	358		885
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	81	81		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	890	890		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
50300225	CONCRETE STRUCTURES	CU YD	68	68		
50500205	FURNISHING STRUCTURAL STEEL	L SUM	1	1		
50700105	TREATED TIMBER	FBM	41	41		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,740	2,740		
50800515	BAR SPLICERS	EACH	40	40		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	94	94		
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	26	26		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	4		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	255	255		
60223800	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1		
60243500	INLETS, SPECIAL, TYPE 3, 6'	EACH	3	3		

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
o:\pwork\pwork\colemm\dms43714\d978065_sht_schedule.dgn		DRAWN -	REVISED -			869	.	Saline	82	6	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			SCALE: NONE		SHEET NO. 2 OF 3 SHEETS		STA. TO STA.	
PLOT DATE = 11/4/2009		DATE -	REVISED -			ILLINOIS FED. AID PROJECT CONTRACT NO. 78065					