

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SALINE CO.	SALINE CO.	SALINE CO.
				ROADWAY RURAL 80% FED 20% STATE	PARKING LANES RURAL 80% FED 20% CITY	ROADWAY RURAL 80% FED 20% STATE
CONSTRUCTION TYPE CODE				I000	I000	I000
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	234	234		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	912.5	912.5		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4		
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6		
* 63200310	GUARDRAIL REMOVAL	FOOT	576	576		
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	100	100		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	16	16		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	4		3
67100100	MOBILIZATION	L SUM	1	0.5		0.5
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5		0.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1			1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5		0.5
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	4		4
* 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	23,228	7,837	120	15,271
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	284		142	142
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,080	2,080		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	116	116		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,945	943		1,002
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10,952	5,528		5,424
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	284		142	142
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,080	2,080		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	116	116		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	23,228	7,837	120	15,271
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	166	97		69
78200420	GUARDRAIL MARKERS, TYPE B	EACH	19	19		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	166	97		69
86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	1	1		
* 88600100	DETECTOR LOOP, TYPE I	FOOT	30	30		
* 89501510	RELOCATE EXISTING FLASHING BEACON	EACH	1	1		

* SPECIALTY ITEM

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 869	SECTION *	COUNTY Saline	TOTAL SHEETS 82	SHEET NO. 7
ar:\pw\work\p\dot\colemm\dms43714\d978065_sht_schedule.dgn		DRAWN -	REVISED -		SCALE: NONE SHEET NO. 3 OF 3 SHEETS STA. TO STA.				CONTRACT NO. 78065				
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT								
PLOT DATE = 11/4/2009		DATE -	REVISED -										