

GENERAL NOTES

IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL EXISTING FIELD DIMENSIONS AND CONDITIONS PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE THICKNESS OF BITUMINOUS MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.

FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES:

ALL ASPHALT:	2.016 TONS/CU. YD.
ALL AGGREGATE:	2.05 TONS/CU. YD.
AGGREGATE PRIME COAT:	0.0015 TONS/SQ. YD.
BITUMINOUS MATERIALS (PRIME COAT):	0.09 GAL./SQ. YD.
RIPRAP (A3&A4):	1.50 TONS/CU. YD.

PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING STRUCTURES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK. THE CONTRACTOR, HOWEVER, WILL BE PAID FOR THE ACTUAL QUANTITY FURNISHED AT THE UNIT PRICE BID FOR THE WORK. EXISTING PLANS ARE AVAILABLE FOR REVIEW AT THE DISTRICT 9 OFFICE.

IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 101.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.

AT ALL LOCATIONS WHERE THE PROPOSED HOT-MIX ASPHALT OR CONCRETE PAVEMENT JOINS AN EXISTING HOT-MIX ASPHALT OR CONCRETE PAVEMENT, A FULL DEPTH SAWED JOINT SHALL BE CONSTRUCTED. THE COST OF THIS JOINT WILL BE INCLUDED IN THE COST OF THE TYPE OF PAVEMENT BEING CONSTRUCTED.

QUANTITIES SHOWN IN THE PLANS FOR BRIDGE DECK GROOVING AND PROTECTIVE COAT INCLUDE THE BRIDGE, THE BRIDGE APPROACH PAVEMENTS, AND THE BRIDGE APPROACH PAVEMENT CONNECTORS (PCC).

PROTECTIVE COAT SHALL BE APPLIED TO THE BRIDGE, THE BRIDGE APPROACH PAVEMENT, AND THE BRIDGE APPROACH PAVEMENT CONNECTOR (PCC), IN ACCORDANCE WITH ARTICLE 503.19 OF THE STANDARD SPECIFICATION. THE SEASONAL EXCEPTION SHALL NOT APPLY. THE PROTECTIVE COAT SHALL BE APPLIED REGARDLESS OF THE CURING METHOD USED. THE RATE OF APPLICATION FOR EACH COAT ON SAW CUT GROOVED AREAS SHALL BE 25 SQUARE YARDS PER GALLON OF MIXTURE.

TREES SHALL BE PRESERVED THROUGHOUT THIS SECTION AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER. GENERALLY, TREES OUTSIDE THE CLEAR ZONE, AND WHICH DO NOT INTERFERE WITH CONSTRUCTION, SHALL NOT BE DISTURBED.

ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE LEFT IN PLACE UNTIL REMOVAL IS REQUIRED TO CONSTRUCT FINAL GRADE LINES.

THE QUANTITY OF SHORT TERM PAVEMENT MARKING SHOWN IN THE PLANS IS BASED ON ONE APPLICATION.

THE DISTRICT BUREAU OF OPERATIONS SHALL BE NOTIFIED AT LEAST 10 DAYS PRIOR TO PLACEMENT OF THE FINAL PAVEMENT MARKINGS. THE BUREAU OF OPERATIONS WILL THEN DETERMINE THE ACTUAL LIMITS TO BE STRIPED AS 'NO PASSING' ZONES.

THE ADVANCE DETECTOR LOOPS ARE TYPICALLY LOCATED 275 FEET IN ADVANCE OF THE STOP BAR. THE BUREAU OF OPERATIONS SHOULD APPROVE THE LOOP LOCATIONS PRIOR TO INSTALLATION.

THE CENTERLINE PAVEMENT MARKING SHOULD BE REMOVED FROM THE STOP BAR TO THE SAND ATTENUATORS OR DRUMS. EDGE LINE PAVEMENT MARKING SHOULD BE REMOVED IF A 10 FOOT LANE WIDTH CANNOT BE MAINTAINED. TEMPORARY EDGE LINES SHOULD BE INSTALLED WHEN THE EDGE LINES ARE REMOVED.

VERTICAL PANELS SHOWN ON STANDARD 701321 WILL NOT BE REQUIRED ON THE STAGE II NEW BRIDGE PARAPET. THE BARRIER WALL REFLECTORS SHALL BE INSTALLED PRIOR TO OPENING TO TRAFFIC.

ANY TIME THE CONCRETE BARRIER IS NOT IN THE PROPER POSITION, FLAGGERS SHALL BE IN PLACE TO CONTROL TRAFFIC. THE TEMPORARY TRAFFIC SIGNALS SHALL BE SET TO FLASH TO RED.

THE ALGEBRAIC DIFFERENCE BETWEEN THE PAVEMENT AND SHOULDER SLOPES SHALL NOT EXCEED 8%.

ON ALL SUPERELEVATED CURVES, THE PROPOSED BASE COURSE WIDENING SHALL BE CONSTRUCTED WITH A SLOPE CONFORMING TO THE RATE OF SUPERELEVATION OF THE EXISTING PAVEMENT.

ALL OBSTRUCTIONS WHICH ARE WITHIN THE CLEAR ZONE SHOWN ON THE TYPICAL SECTION, AND ARE NOT SHIELDED BY THE PROPOSED GUARDRAIL, SHALL BE REMOVED BETWEEN STATION 42+71.71 AND STATION 49+36.91. TYPICAL OBSTRUCTIONS ARE HEADWALLS, FOUNDATIONS, ETC. WHICH PROJECT 100 mm (4 IN.) OR MORE ABOVE THE GROUNDLINE; AND TREES WHICH WILL MATURE TO A DIAMETER OF 100 mm (4 IN.) OR GREATER.

THE EXISTING ROAD SIGNS THAT INTERFERE WITH CONSTRUCTION SHALL BE RELOCATED AS DIRECTED BY THE ENGINEER. AFTER THE CONSTRUCTION IS COMPLETED, THE CONTRACTOR WILL REPLACE THE SIGNS AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

COMMITMENTS: NONE AS OF 10/16/08

STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
420001-07	PAVEMENT JOINTS
420401-08	BRIDGE APPROACH PAVEMENT CONNECTOR
482001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
515001-03	NAME PLATE FOR BRIDGES
542301-02	PRECAST REINFORCED CONCRETE FLARED END SECTION
630001-08	STEEL PLATE BEAM GUARDRAIL
630201-06	PCC/HMA STABILIZATION AT STEEL PLATE BEAM GUARDRAIL
630301-05	SHOULDER WIDENING FOR TYPE 1, (SPECIAL) GUARDRAIL TERMINALS
631031-08	TRAFFIC BARRIER TERMINAL, TYPE 6
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER & MOUNTING DETAILS
666001-01	RIGHT OF WAY MARKERS
701001-02	OFF ROAD OPERATIONS, 2L, 2W, MORE THAN 4.5 (15') AWAY
701006-03	OFF-ROAD OPERATIONS, 2L 2W, 4.5m (15') TO PAVEMENT EDGE
701011-02	OFF ROAD MOVING OPERATIONS 2L, 2W, DAY ONLY
701201-03	LANE CLOSURE, 2L 2W, DAY ONLY, ON-ROAD TO 600mm (24") OFF-ROAD, FOR SPEEDS > 45 MPH
701301-03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS-DAY ONLY
701311-03	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701321-10	LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
701326-03	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS > 45MPH
701901-01	TRAFFIC CONTROL DEVICES
704001-06	TEMPORARY CONCRETE BARRIER
780001-02	TYPICAL PAVEMENT MARKINGS
601101-01	

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS; GENERAL NOTES; STANDARDS
3-4	SUMMARY OF QUANTITIES
5-7	TYPICAL SECTIONS
8-9	SCHEDULE OF QUANTITIES
10	PLAN-PROFILE
11	STAGE CONSTRUCTION PLAN
12	BITUMINOUS SHOULDER PLAN & GUARDRAIL PLAN
13	EROSION CONTROL PLAN
14	RIGHT OF WAY
15	DETOUR SIGNING SHEET
16-33	STRUCTURE PLANS- SN 028-0084 (No sheet 33)
34-35	DETAILS
36-40	CROSS SECTIONS

Location(s):	- Hot-Mix Asphalt Surface Course
Mixture Use(s):	- Hot-Mix Asphalt Surface Course, Mix D, N90
AC/PG:	- PG64-22
RAP % (Max):	- 10
Design Air Voids:	- 4.0%, 90 Gyration Design
Mixture Composition: (Gradation Mixture)	- IL-9.5 mm or IL 12.5 mm
Friction Aggregate:	- D Surface

Location(s):	- Leveling Binder (Machine Method), N90
Mixture Use(s):	- Hot-Mix Asphalt Surface Course, Mix C, N90
AC/PG:	- PG64-22
RAP % (Max):	- 10
Design Air Voids:	- 4.0%, 90 Gyration Design
Mixture Composition: (Gradation Mixture)	- IL-9.5 mm or IL 12.5 mm
Friction Aggregate:	- None

Location(s):	- Hot-Mix Asphalt Shoulders
Mixture Use(s):	- Hot-Mix Asphalt Shoulders
AC/PG:	- PG58-22
RAP % (Max):	- 50
Design Air Voids:	- 2.0%, 30 Gyration Design
Mixture Composition: (Gradation Mixture)	- HMA Shoulders
Friction Aggregate:	- None

Prepared By: *Dennis W. Hillman*
DISTRICT STUDIES & PLANS ENGINEER

Examined By: *Thomas Reed's Emery*
DISTRICT LAND ACQUISITION ENGINEER

Examined By: *Carrie Nelson*
DISTRICT PROGRAM DEVELOPMENT ENGINEER

Examined By: *Kevin Wiley*
DISTRICT OPERATIONS ENGINEER

Examined By: *John Smith*
DISTRICT CONSTRUCTION ENGINEER

Examined By: *Angela B. Baker*
DISTRICT MATERIALS ENGINEER

Examined By: *John Smith*
DISTRICT PROJECT IMPLEMENTATION ENGINEER

Examined By: *Thomas Reed's Emery*
ASSISTANT REGIONAL ENGINEER

Approved By: *Mary L. Lomis*
DEPUTY DIRECTOR OF HIGHWAYS, REGION ENGINEER

Oct 13 2009
DATE

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES; HIGHWAY STANDARDS IL 34 OVER UNNAMED STREAM			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN -	REVISED -		SCALE: N/A	SHEET NO. OF SHEETS	STA.	TO STA.	869	101B-1	FRANKLIN	40	2
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -										
	PLOT DATE = #DATE#	DATE -	REVISED -										
								FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT				