

SUMMARY OF QUANTITIES

| X | CODE NUMBER | PAY ITEM | UNIT | QUANTITY | | | |
|---|-------------|--|----------|----------|-----------------|------------------------|-------------|
| | | | | TOTAL | ROADWAY 1000-2A | TRAFFIC SIGNAL Y031-1F | |
| | | | | | | CHESTNUT LANE | CHURCH ROAD |
| | 20200100 | EARTH EXCAVATION | CU YD | 120 | 120 | | |
| | 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 40 | 40 | | |
| | 20700420 | POROUS GRANULAR EMBANKMENT, SUBGRADE | CU YD | 40 | 40 | | |
| | 28000510 | INLET FILTERS | EACH | 4 | 4 | | |
| | 31101200 | SUB-BASE GRANULAR MATERIAL, TYPE B 4" | SQ YD | 200 | 200 | | |
| | 35501308 | HOT-MIX ASPHALT BASE COURSE, 6" | SQ YD | 40 | 40 | | |
| | 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 10 | 10 | | |
| | 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 16 | 16 | | |
| | 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 8 | 8 | | |
| | 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 526 | | 526 | |
| | 42400800 | DETECTABLE WARNINGS | SQ FT | 48 | | 48 | |
| | 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 120 | | 120 | |
| | 44000600 | SIDEWALK REMOVAL | SQ FT | 140 | | 140 | |
| | 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 97 | | 97 | |
| | 44003100 | MEDIAN REMOVAL | SQ FT | 50 | 50 | | |
| | 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 48 | | 48 | |
| | 67100100 | MOBILIZATION | LUMP SUM | 1 | 1.0 | | |
| | 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 | | |
| | 70102622 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701502 | L SUM | 1 | 1 | | |
| | 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | |
| | 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | | |
| | 70300200 | TEMPORARY PAVEMENT MARKING | FOOT | 1,000 | 1,000 | | |
| X | 72000100 | SIGN PANEL - TYPE 1 | SQ FT | 18 | | 18 | |
| | 72000200 | SIGN PANEL - TYPE 2 | SQ FT | 25 | | 25 | |
| X | 72400100 | REMOVE SIGN PANEL ASSEMBLY - TYPE A | EACH | 2 | 2 | | |
| X | 72400310 | REMOVE SIGN PANEL - TYPE 1 | SQ FT | 23 | 23 | | |
| X | 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 178 | 178 | | |
| X | 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 4,950 | 4,950 | | |
| X | 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 1,150 | 1,150 | | |
| X | 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 310 | 310 | | |
| X | 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 105 | 105 | | |
| X | 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 107 | 107 | | |
| X | 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 1,400 | 1,400 | | |
| X | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 55 | 55 | | |
| | 81000600 | CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL | FOOT | 1,672 | | 871 | 801 |
| | 81000700 | CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 50 | | 50 | |
| | 81000800 | CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL | FOOT | 24 | | 24 | |
| | 81001100 | CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL | FOOT | 8 | | 8 | |
| | 81018500 | CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL | FOOT | 608 | | 42 | 566 |
| | 81018700 | CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL | FOOT | 59 | | 59 | |
| | 81018900 | CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL | FOOT | 324 | | 324 | |

X INDICATES SPECIALTY ITEMS
 INDICATES SPECIAL PROVISION

FILE NAME = S:\JUL 0908 - 6995A\699A\023\Micro\shheets\Summary.dgn

STRAND CONSULTANTS, INC.
 ENGINEERS
 1170 SOUTH HOUBOLT ROAD
 JOLIET, ILLINOIS 60431
 (815) 744-4200

| | | |
|-----------------------------|------------|-----------|
| USER NAME = edamm | DESIGNED - | REVISED - |
| PLOT SCALE = 20,0000' / IN. | DRAWN - | REVISED - |
| PLOT DATE = 10/27/2009 | CHECKED - | REVISED - |
| | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|---------------------|----------------|--------|---------------------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 0332 | 06-00015-00-TL | WILL | 31 | 3 |
| FED. ROAD DIST. NO. | | | ILLINOIS FED. AID PROJECT | |
| CONTRACT NO. 83909 | | | | |