


SUMMARY OF QUANTITIES

X	•	CODE NUMBER	PAY ITEM	UNIT	QUANTITY			
					TOTAL	ROADWAY 1000-2A	TRAFFIC SIGNAL Y031-1F	INTERCONNECT Y031-1F
		81400100	HANDHOLE	EACH	6		4	2
		81400200	HEAVY-DUTY HANDHOLE	EACH	3		3	
		81400300	DOUBLE HANDHOLE	EACH	2		2	
		81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,754		953	801
		85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1	
		85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1		1	
		86000105	MASTER CONTROLLER (SPECIAL)	EACH	1			1
		86400100	TRANSCEIVER - FIBER OPTIC	EACH	2		1	1
		87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	670		670	
		87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,241		1,241	
		87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,243		1,243	
		87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	926		926	
		87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1,660		1,660	
		87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	215		215	
		87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1		1	
		87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1		1	
		87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1	
		87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1	
		87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1	
		87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4	
		87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4	
		87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60		60	
		87900200	DRILL EXISTING HANDHOLE	EACH	1			1
		88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	5		5	
		88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1	
		88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		3	
		88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	3		3	
		88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2	
		88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	3		3	
		88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8	
		88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8	
		88600100	DETECTOR LOOP, TYPE I	FOOT	795		795	
		88800100	PEDESTRIAN PUSH-BUTTON	EACH	5		5	
		X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51		
		X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1,735			1,735
		X0324007	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1			1
		X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1		1	
		X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1		1	
		X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MMI2F SM12F	FOOT	1,735			1,735
		X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	760		760	
		44004600	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	170		170	
		Z0013798	CONSTRUCTION LAYOUT	LUMP SUM	1	1		
		XX005431	LOCATE UNDERGROUND UTILITY	EACH	5	5		

X INDICATES SPECIALTY ITEMS

• INDICATES SPECIAL PROVISION

FILE NAME = SA:\DL\65900-6599\6534\003\Micro\sheetis\Summary2.dgn



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200
USER NAME = adam
DESIGNED -
DRAWN -
CHECKED -
DATE -
REVISED -
REVISED -
REVISED -
REVISED -
PLOT SCALE = 20.0000' / IN.
PLOT DATE = 10/27/2009

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0332	06-00015-00-TL	WILL	31	4
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 83909	