

**TREE REMOV 6-15**

LOCATION	UNIT	REMARKS
RT 6+57	14	
RT 6+60	8	
RT 6+64	8	
RT 6+77	8	
RT 6+96	6	
RT 7+00	6	
RT 7+01	6	
RT 7+04	6	
RT 7+07	6	
LT 10+20	10	
PROJECT TOTAL	78	

**TREE REMOV OVER 15**

LOCATION	UNIT	REMARKS
RT 5+55	18	
RT 5+60	18	
RT 8+18	40	
LT 13+30	24	
PROJECT TOTAL	100	

**EARTH EXCAVATION**

LOCATION	CU YD	REMARKS
RALSTON RD	2960	
BLUEBONNET DR	493	
PROJECT TOTAL	3453	

**TRENCH BACKFILL**

LOCATION	CU YD	REMARKS
LT & RT 2+00	13	
LT 6+16	6	
RT 6+20	11	
LT 7+91	7	
RT 7+93	5	
RT 9+18	5	
RT 10+93	5	
LT 10+96	13	
RT 12+63	5	
LT 12+65	13	
LT 14+92	4	
RT 14+93	4	
LT & RT 24+06	15	
PROJECT TOTAL	106	

**SEEDING CL 1A SPL**

LOCATION	ACRE	REMARKS
RT 1+00 - 8+00	0.11	RALSTON
LT 1+00 - 8+17	0.14	
RT 9+00 - 16+14	0.24	
LT 9+14 - 16+14	0.11	
RT 20+00 - 22+90	0.04	BLUEBONNET
LT 20+00 - 22+95	0.10	
RT 23+78 - 28+94	0.09	
LT 23+75 - 28+72	0.17	
PROJECT TOTAL	1	

**TEMP DITCH CHECKS**

LOCATION	FOOT	REMARKS
RT 20+00	15	
PROJECT TOTAL	15	

**PERIMETER EROS BAR**

LOCATION	FOOT	REMARKS
RT 1+00 - 8+00	704	
LT 1+00 - 8+17	714	
RT 9+00 - 16+14	748	
LT 9+14 - 16+14	647	
PROJECT TOTAL	2813	

**INLET & PIPE PROTECT**

LOCATION	EACH	REMARKS
LT & RT 2+00	2	RALSTON
LT 6+18	1	
RT 6+22	1	
LT 7+91	1	
RT 7+93	1	
RT 9+18	1	
RT 10+94	1	
LT 11+03	1	
LT 14+92	1	
RT 14+93	1	
RT 12+62	1	
LT 12+65	1	
LT 19+89	1	BLUEBONNET
LT 21+18	1	
LT 22+15	1	
RT 24+12	1	
LT 24+39	1	
RT 24+78	1	
LT 25+21	1	
LT 26+11	1	
LT 27+00	1	
LT 27+78	1	
LT 28+75	1	
PROJECT TOTAL	25	

**AGG BASE CSE B**

LOCATION	TON	REMARKS
LT 1+45 - 8+27	329	RALSTON
RT 1+45 - 8+37	614	
LT 8+83 - 15+69	596	
RT 8+80 - 15+69	347	
LT 20+00 - 23+02	167	BLUEBONNET
RT 20+00 - 23+02	113	
LT 23+66 - 28+72	177	
RT 23+66 - 28+72	231	
1+00-16+14 & 20+00-28+72	271	DRIVEWAYS
RT 1+00-6+14	75	MAILBOX TURNOUT
RT 11+70-12+36	7	
PROJECT TOTAL	2927	

**BIT MATLS PR CT**

LOCATION	TON	REMARKS
1+00-16+14 & 20+00-28+72	2.80	EXISTING BITUMINOUS RALSTON
LT 1+45 - 8+27	0.70	
RT 1+45 - 8+37	1.10	
LT 8+83 - 15+69	1.00	BLUEBONNET
RT 8+80 - 15+69	0.70	
LT 20+00 - 22+99	0.35	
RT 20+00 - 23+08	0.25	
LT 23+60 - 28+72	0.35	
RT 23+67 - 28+72	0.45	DRIVEWAYS
1+00-16+14 & 20+00-28+72	0.30	
PROJECT TOTAL	8	

**AGG PR CT**

LOCATION	TON	REMARKS
1+00-16+14 & 20+00-28+72	7	
PROJECT TOTAL	7	

**LEVEL BIND MM N50**

LOCATION	TON	REMARKS
20+25 - 23+00	26	
PROJECT TOTAL	26	

**LEVEL BIND MM N70**

LOCATION	TON	REMARKS
1+25 - 4+50	157	
PROJECT TOTAL	157	

**HMA SURF REM BUTT JT**

LOCATION	SQ YD	REMARKS
1+00 - 1+15	43	
15+84 - 16+14	87	
20+00 - 20+15	43	
28+57 - 28+72	27	
PROJECT TOTAL	199	

**TEMPORARY RAMP**

LOCATION	SQ YD	REMARKS
1+00 - 1+05	15	
15+09 - 16+14	15	
20+10 - 20+15	15	
28+67 - 28+72	13	
PROJECT TOTAL	58	

**HMA BC IL-12.5 N50**

LOCATION	TON	REMARKS
RT 1+00 - 6+14	83	MAIL TURNOUT
RT 11+70 - 12+36	8	BLUEBONNET
LT 20+00 - 23+02	25	
RT 20+00 - 23+02	17	
LT 23+66 - 28+72	26	
RT 23+66 - 28+72	34	
PROJECT TOTAL	193	

**HMA BC IL-19.0 N70**

LOCATION	TON	REMARKS
LT 1+45 - 8+27	288	
RT 1+45 - 8+37	548	RALSTON
LT 8+83 - 15+69	549	
RT 8+80 - 15+69	320	
PROJECT TOTAL	1705	

**HMA SC "C" N50**

LOCATION	TON	REMARKS
LT & RT 20+00 - 23+02	112	BLUEBONNET
LT & RT 23+66 - 28+72	177	
RT 1+00 - 6+14	28	MAIL TURNOUT
RT 11+70 - 12+36	3	
PROJECT TOTAL	320	

**HMA SC "D" N70**

LOCATION	TON	REMARKS
LT & RT 1+00 - 16+14	644	RALSTON
PROJECT TOTAL	644	

**INCIDENTAL HMA SURF**

LOCATION	TON	REMARKS
1+00-16+14 & 20+00-28+72	47	DRIVEWAYS
PROJECT TOTAL	47	

**PCC DRIVEWAY PAVT 6**

LOCATION	SQ YD	REMARKS
LT 1+23	25	RALSTON
LT 1+56	28	DRIVEWAY APRONS
LT 3+76	24	
LT 4+07	24	
LT 5+97	28	
LT 12+11	40	
LT 13+14	40	
LT 13+87	52	
LT 16+07	42	BLUEBONNET DRIVEWAY
LT 26+64	45	
PROJECT TOTAL	348	

**PC CONC SIDEWALK 4**

LOCATION	SQ FT	REMARKS
LT 15+69	89	
PROJECT TOTAL	89	

**DRIVE PAVEMENT REM**

LOCATION	SQ YD	REMARKS
LT 26+64	54	
PROJECT TOTAL	54	

**COMB CURB GUTTER REM**

LOCATION	FOOT	REMARKS
LT 1+00 - 8+05	705	
RT 1+00 - 8+23	701	
LT 9+04 - 16+14	710	
RT 8+78 - 16+14	738	
PROJECT TOTAL	2854	

**SIDEWALK REM**

LOCATION	SQ FT	REMARKS
LT 14+70	96	
LT 15+69	96	
PROJECT TOTAL	192	

**STRIP REF CR CON TR A**

LOCATION	FOOT	REMARKS
LT 1+45 - 8+27	700	
RT 1+45 - 8+37	693	
LT 8+83 - 15+69	692	
RT 8+80 - 15+69	701	
PROJECT TOTAL	2786	

**PIPE CULVERT REMOV**

LOCATION	FOOT	REMARKS
LT 21+00	22	
LT 22+00	21	
LT 24+78	20	
LT 25+66	21	
LT 26+64	29	
LT 27+63	20	
LT 28+62	21	
PROJECT TOTAL	154	

**P CUL 1 CS/A CP 15**

LOCATION	FOOT	REMARKS
LT 21+00	30	
PROJECT TOTAL	30	

**P CUL 1 CS/A EQ RS 15**

LOCATION	FOOT	REMARKS
LT 22+00	25	
LT 27+63	25	
LT 28+62	27	
PROJECT TOTAL	78	

**PRC FLAR END SEC 15**

LOCATION	EACH	REMARKS
RT 24+78	1	
LT 27+00	1	
PROJECT TOTAL	2	

**STORM SEW CL A 1 12**

LOCATION	FOOT	REMARKS
LT & RT 2+00	34	
LT 6+18	9	
RT 6+22	21	
LT 7+91	16	
RT 7+93	21	
RT 9+18	11	
RT 10+94	8	
LT 11+03	27	
RT 12+62	8	
LT 12+65	10	
LT 14+92	2	
RT 14+93	3	
PROJECT TOTAL	170	

**STORM SEW CL A 1 15**

LOCATION	FOOT	REMARKS
LT 7+91	16	DRIVEWAY GRATE
LT 7+91 - 8+35	57	
LT & RT 24+04	51	
LT 24+00-24+39	39	
RT 24+10-24+78	60	
LT 24+39-25+21	82	
LT 25+21-26+11	98	
LT 26+11-27+00	81	
PROJECT TOTAL	484	

**STORM SEWER REM 12**

LOCATION	FOOT	REMARKS
LT 7+90	6	
LT 7+90-8+20	62	
LT 8+20-8+33	25	
LT 8+20-8+79	59	
LT 10+89	7	
PROJECT TOTAL	159	

**INLETS TA T8G**

LOCATION	EACH	REMARKS
LT 24+39	1	
LT 25+21	1	
LT 26+11	1	
PROJECT TOTAL	3	

**INLETS SPL**

LOCATION	EACH	REMARKS
RT 2+00	1	
RT 6+18	1	
RT 14+93	1	
PROJECT TOTAL	3	

**INLETS SPL N2**

LOCATION	EACH	REMARKS
LT 2+00	1	
LT 6+18	1	
LT 7+91	1	
RT 7+93	1	
RT 9+18	1	
RT 10+84	1	
LT 11+03	1	
RT 12+62	1	
LT 12+65	1	
LT 14+92	1	
LT 24+00	1	
RT 24+10	1	
PROJECT TOTAL	12	

**MAN ADJUST**

LOCATION	EACH	REMARKS
LT 0+91	1	STORM
LT 3+90	1	STORM
LT 6+83	1	TELEPHONE
LT 7+90	1	STORM
LT 8+57	1	SANITARY
LT 9+18	1	STORM
LT 10+84	1	SANITARY
LT 10+89	1	STORM
LT 12+65	1	STORM
LT 13+07	1	SANITARY
RT 22+49	1	SANITARY
LT 28+15	1	SANITARY
PROJECT TOTAL	12	

**VALVE BOX ADJ**

LOCATION	EACH	REMARKS
LT 3+83	1	
RT 8+17	1	
LT 8+80	1	
RT 13+39	1	
LT 22+27	1	
PROJECT TOTAL	5	

**REMOV MANHOLES**

LOCATION	EACH	REMARKS
LT 14+92	1	
PROJECT TOTAL	1	

**REMOV INLETS**

LOCATION	EACH	REMARKS
LT 6+15	1	
RT 6+17	1	
LT 7+90	1	
RT 7+92	1	
RT 9+18	1	
LT 10+89	1	
RT 10+92	1	
RT 12+63	1	
LT 12+65	1	
LT 14+92	1	
RT 14+93	1	
PROJECT TOTAL	11	

**COMB CC&G TB6.24**

LOCATION	FOOT	REMARKS
LT 1+00 - 8+37	764	
RT 1+00 - 8+31	749	
LT 8+83 - 16+14	758	
RT 8+77 - 16+14	766	
PROJECT TOTAL	3037	

**TEMP PT PAVT MK L&S**

LOCATION	SQ FT	REMARKS
RT 6+40-7+70	31.2	
PROJECT TOTAL	31.2	