85478

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5031	04-00344-00-TL	WINNEBAGO	28	10
	ILLINOIS	CONTRACT NO.		85478

STRIPE 4" WHITE
STATION LT -0+84 TO 1+00

STRIPE 4" WHITE
STATION LT 0+00 TO 1+00

STRIPE 4" DOUBLE YELLOW
STATION 0+00 TO 1+00

40'

26'-6"

60'

1.5' STUB
STA 1+45

12" YELLOW

4" YELLOW

4" WHITE EDGE LINE

20'

40'

STA 4+14.96
8" BT

TWO-WAY YELLOW MARKER
(TYPICAL)

2' - 6' SKIP DASH 8" WHITE

STA 6+14.90

STA 6+14.97

8" WHITE

ONE-WAY WHITE MARKER
(TYPICAL)

◁ ONE-WAY RAISED REFLECTIVE PAVEMENT MARKER
◆ TWO-WAY RAISED REFLECTIVE PAVEMENT MARKER

GRAPHIC SCALE 1"=20'
0 20 40 60

RALSTON ROAD

24" WHITE

STA 7+96.06

STA 8+01.06

STA 9+12.97

STA 9+17.97

STA 10+98.97

STA 10+99.12

PT 22+65.64

STRIPING PLAN

Arnold Lundgren & Associates
Professional Engineers and Land Surveyors
Illinois Design Firm No. 184-002889
803 N. Church Street • Rockford, IL 61103
(815) 968-8881 • Fax (815) 962-6409
www.arnoldlundgren.com

1928–2006 78th ANNIVERSARY

DATE	05/17/06
BY	VRL
APPROVED	RFA
ORDER NO.	22475

REVISIONS
6-5-06 PER IDOT COMMENTS VRL
3-16-09 REVISED PER WINNEBAGO COUNTY HIGHWAY DEPT. VRL
4-22-09 REVISED PER WINNEBAGO COUNTY HIGHWAY DEPT. VRL
10-15-09 REVISED PER IDOT COMMENTS VRL
11-09-09 REVISED PER IDOT COMMENTS VRL