FIXTURE#	P1	P2	P3	P4	P5	P6	P7	P8	P9	P10	P11
FIXTURE TYPE	B	B	B	B	B	B	B	B	B	B	B
MOUNTING HEIGHT	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	NOT	NOT	15' 3-5/8"
# OF LUMINAIRES ON POLE TOP	2	2	2	2	2	2	2	2	USED	USED	2
CONNECTION TYPE	2	2	2	2	2	2	2	2	–	–	2
CIRCUIT CONNECTION	1,3	2,4	3,5	4,6	5,1	6,2	1,3	2,4	–	–	3,5
STATION	20+02.00	20+02.56	20+88.08	20+88.36	20+00.07	20+00.35	19+44.74	19+45.45	–	–	18+60.55
OFFSET	22.00 R	22.00 L	22.07 R	21.96 L	22.00 R	22.10 L	21.65 R	22.45 L	–	–	22.36 R

FIXTURE#	P12	P13	P14	P15	P16	P17	P18	P19	P20	P21	P23	P25	P26
FIXTURE TYPE	B	B	B	B	B	B	B	B	B	B	B	B	B
MOUNTING HEIGHT	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	15' 3-5/8"	NOT	NOT	15' 3-5/8"	15' 3-5/8"
# OF LUMINAIRES ON POLE TOP	2	2	2	2	2	2	2	2	2	USED	USED	2	2
CONNECTION TYPE	2	2	2	2	2	1	1	2	2	–	–	2	2
CIRCUIT CONNECTION	4,6	5,1	6,2	1,3	2,4	3,5	4,6	7,9	8,10	–	–	7,9	10,12
STATION	18+61.30	18+02.84	18+03.22	17+12.93	17+13.15	16+00.42	16+00.77	15+42.34	15+43.04	–	–	14+58.17	14+58.93
OFFSET	21.63 L	22.00 R	22.00 L	22.00 R	22.00 L	22.00 R	22.00 L	21.63 R	22.37 L	–	–	22.22 R	21.78 L

FIXTURE#	P27	P28	P29	P30	P31	P32	P33	P34	P35	P36	P37	P38	P39	P40	P41	P42	P43
FIXTURE TYPE	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
MOUNTING HEIGHT	14'	14'	14'	14'	14'	14'	14'	14'	14'	14'	NOT	NOT	NOT	NOT	14'	14'	14'
# OF LUMINAIRES ON POLE TOP	2	2	2	2	2	2	2	2	2	2	USED	USED	USED	USED	2	2	2
CONNECTION TYPE	2	2	2	2	2	2	2	2	2	2	–	–	–	–	1	1	1
CIRCUIT CONNECTION	9,11	12,8	11,7	8,10	7,9	10,12	9,11	12,8	11,7	8,10	–	–	–	–	11,7	8,10	10,12
STATION	14+23.88	14+24.15	13+33.17	13+33.38	12+65.58	12+65.90	11+74.87	11+75.15	11+42.16	11+42.43	–	–	–	–	10+57.64	10+57.91	10+71.52
OFFSET	22.01 R	22.00 L	21.90 R	22.01 L	21.64 R	22.03 L	21.27 R	22.02 L	20.83 R	22.23 L	–	–	–	–	20.29 R	22.77 L	90.25 L

FIXTURE#	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12
FIXTURE TYPE	D	D	D	D	D	D	D	D	D	D	NOT	NOT
MOUNTING HEIGHT	19'-7"	19'-7"	19'-7"	19'-7"	19'-7"	19'-7"	19'-7"	19'-7"	19'-7"	19'-7"	USED	USED
# OF LUMINAIRES ON POLE TOP	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	–	–
CONNECTION TYPE	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	–	–
CIRCUIT CONNECTION	25	25	25	25	25	25	25	25	25	25	–	–
STATION	14+58.00	15+43.00	16+00.00	17+13.00	18+03.00	18+61.00	19+45.00	20+00.00	20+88.00	22+02.00	–	–
OFFSET	0	0	0	0	0	0	0	0	0	0	–	–

SHIVE-HATTERY
ARCHITECTURE - ENGINEERING
http://www.shive-hattery.com
Iowa - Illinois - Missouri - Nebraska
ILLINOIS FIRM NUMBER: 184-000214

DAVID M TERPSTRA
REGISTERED
No. 062-051804
STATE OF ILLINOIS
PROFESSIONAL ENGINEER

SIGNATURE

11/30/2009
EXPIRATION DATE

10-16-09
DATE

CITY OF MOLINE ILLINOIS

CITY OF MOLINE
DEPARTMENT OF PUBLIC WORKS – ENGINEERING DIVISION
3635 4TH AVENUE, MOLINE, IL 61265
(309) 797-0700

CITY ENGINEER – SCOTT HINTON, P.E.

5TH AVENUE
ELECTRICAL DETAILS

Date	Revision

Date 09-30-09	Sheet 35 OF 50
Scale NOT TO SCALE	
MFT PROJ. # 09-00242-00RP	DESIGNER DFW