

LIST OF QUANTITIES

Item Number	Description	Units	Construction Type Code	
			J000	Non Part 1000
20200100	Earth Excavation	C.Y.	992	
20800150	Trench Backfill	C.Y.	89	
21001000	Geotechnical Fabric for Ground Stabilization	S.Y.	4,188	
25200100	Sodding	S.Y.	2,443	
28000500	Inlet and Pipe Protection	Each	61	
31101900	Sub-Base Granular Material, Type C	Ton	1,275	
35100100	Aggregate Base Course, Type A	Ton	838	
40600100	Bituminous Materials (Prime Coat)	Gal.	103	
40600400	Mixture For Cracks, Joints, And Flangeways	Ton	10	
40800625	Leveling Binder (Machine Method) N50	Ton	2,189	
40603335	Hot-Mix Asphalt Surface Course Mix "D" N50	Ton	1,926	
40800050	Incidental Hot-Mix Asphalt Surfacing	Ton	2	
42300200	PCC Driveway Pavement, 6"	S.Y.	453	
42300710	Portland Cement Concrete Driveway Pavement, 6 Inch, Special	S.Y.	16	
42400200	PCC Sidewalk, 5"	S.F.	2,800	
42400800	Detectable Warnings	S.F.	160	
44000000	Hot-Mix Asphalt Surface Correction	S.Y.	6,678	
44000100	Pavement Removal	S.Y.	3,404	
44000200	Driveway Pavement Removal	S.Y.	463	
44000500	Combination Curb & Gutter Removal	Ft.	1,271	
44000600	Sidewalk Removal	S.F.	2,727	
* 56100600	Watermain, 6"	Ft.		119
* 56100700	Watermain, 8"	Ft.		3
* 56100800	Watermain, 10"	Ft.		48
* 56400500	Fire Hydrant to Be Removed	Each		3
* 56400600	Fire Hydrant	Each		6
56500600	Domestic Water Service Boxes To Be Adjusted	Each	3	
60107600	Pipe Underdrains 4"	Ft.	348	
60218400	Manhole, Type A, 4' Diameter, Type 1 Frame, Closed Lid	Each	6	
60221100	Manhole, Type A, 5' Diameter, Type 1 Frame, Closed Lid	Each	2	
60250200	Catch Basin, to Be Adjusted	Each	9	
60255500	Manhole, to Be Adjusted	Each	12	
60266600	Valve Boxes to be Adjusted	Each	11	
60500040	Removing Manhole	Each	3	
60500070	Removing Manhole To Maintain Flow	Each	8	
60500080	Removing Catch Basin To Maintain Flow	Each	14	
60609500	Combination Concrete Curb & Gutter, Type M-6.12 (Modified)	Ft.	1,271	
63301000	Remove And Re-Erect Steel Plate Beam Guard Rail	Ft.	24	
67100100	Mobilization	L.S.	1	
70103700	Traffic Control Complete	L.S.	1	
70300200	Temporary Pavement Marking, Line, 4" Yellow	Ft.	20,270	
70301000	Work Zone Pavement Marking Removal	S.F.	6,689	
* 78000200	Thermoplastic Pavement Marking-Line, 4"	Ft.	2,040	
* 78000650	Thermoplastic Pavement Marking-Line, 24"	Ft.	163	
* 78001130	Paint Pavement Marking- Line, 6"	Ft.	435	
* 78301180	Paint Pavement Marking- Line, 24"	Ft.	122	
LR420129	PCC Pavement, 8", (Special) With Integral Curb	S.Y.	2,376	
* X0840000	Sanitary Sewer Removal, 8"	Ft.		10
* XX005003	Ductile Iron Water Main Fitting - 10" X 6" Tee	Each		4
XX005764	Catch Basin, Single	Each	14	
* XX006077	Gate Valve And Box, 6"	Each		7
* XX006241	Gate Valve And Box, 8"	Each		1
XX007379	Cleanout To Be Removed	Each	1	
* XX007382	Cut And Cap Existing Water Main (6")	Each		1
* XX007520	Gate Valve and Box to Be Removed	Each		8
* XX007523	Compression Pipe Coupling, 8"	Each		2
* XX007524	Gate Valve And Box, 10"	Each		11
XX007530	PCC Base Course, 8", With Integral Curb	S.Y.	1,028	
* Z0056900	Sanitary Sewer, 8"	Ft.		10
* XX008235	Tapping Sleeve, Tee, Class 350, DIP, MJ, 10"x6"	Each		2
* XX008236	Solid Sleeve, Class 350, DIP, MJ, 10"	Each		7
XX008237	Catch Basin, Single, to Be Adjusted, W/Type C Grate	Each	24	
XX008238	Catch Basin, Double, to Be Adjusted	Each	5	
XX008239	Catch Basin, Double, to Be Adjusted, W/Type C Grate	Each	14	

LEGEND

	EXISTING DECIDUOUS TREE
	EXISTING EVERGREEN TREE
	EXISTING BUSH
	EXISTING SIGN
	EXISTING DOMESTIC SERVICE VALVE
	EXISTING WATER VALVE
	PROPOSED WATER VALVE
	EXISTING FIRE HYDRANT
	PROPOSED FIRE HYDRANT
	EXISTING GAS VALVE
	EXISTING POWER POLE
	EXISTING LIGHT POLE
	EXISTING TRAFFIC SIGNAL
	EXISTING HANDHOLE
	EXISTING TRAFFIC SIGNAL CONTROLLER
	EXISTING SINGLE CATCH BASIN
	EXISTING DOUBLE CATCH BASIN
	EXISTING SANITARY MANHOLE
	EXISTING SANITARY CLEANOUT
	EXISTING STORM MANHOLE
	EXISTING WATER MANHOLE
	EXISTING TELEPHONE MANHOLE
	EXISTING SANITARY SEWER
	PROPOSED SANITARY SEWER
	EXISTING STORM SEWER
	PROPOSED STORM SEWER
	PROPOSED PIPE UNDERDRAIN
	EXISTING WATER MAIN
	PROPOSED WATER MAIN
	EXISTING GAS MAIN
	EXISTING ELECTRICAL CONDUIT
	EXISTING FIBER OPTIC CONDUIT
	EXISTING TELEPHONE DUCT
	EXISTING TELEPHONE CONDUIT
	EXISTING R.O.W. LINE
	BITUMINOUS SURFACE REMOVAL
	PAVEMENT REMOVAL & PCC BASE COURSE
	PAVEMENT REMOVAL & PCC PAVEMENT
	SIDEWALK REMOVAL & REPLACEMENT
	PCC CURB RAMP
	PCC DRIVEWAY REMOVAL & REPLACEMENT
	PCC CURB AND GUTTER REMOVAL & REPLACEMENT
	DETECTABLE WARNINGS

8597
L.A. # 09-00186-00-RS
QUANTITIES & LEGEND

CITY OF ROCK ISLAND
ENGINEERING DIVISION

30th Street Resurfacing
31st Avenue to Blackhawk Road

Job Number	2592	Date	3-18-2009
Computer Drawing Name	2592 (0) Lag.dwg	By	msw
		Sheet	6
		OF	41