

SUMMARY OF QUANTITIES				ARRA		
SPECIALTY ITEM	SPECIAL PROVISION	CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
	*	20200100	EARTH EXCAVATION	CU YD	3,889	3,889
	*	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,318	2,318
	*	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	440	440
	*	20800150	TRENCH BACKFILL	CU YD	114	114
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	150	150
		21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	698	698
	*	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	100	100
	*	21400100	GRADING AND SHAPING DITCHES	FOOT	2,244	2,244
		25000210	SEEDING, CLASS 2A	ACRE	1.9	1.9
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	171	171
		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	171	171
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	171	171
		25100630	EROSION CONTROL BLANKET	SQ YD	10,222	10,222
	*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400	400
		<del>28000300</del>	<del>TEMPORARY DITCH CHECKS</del>	<del>FOOT</del>	<del>630</del>	<del>630</del>
		28000400	PERIMETER EROSION BARRIER	FOOT	1,550	1,550
	*	28000500	INLET AND PIPE PROTECTION	EACH	6	6
		28100105	STONE RIPRAP, CLASS A3	SQ YD	100	100
		30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	4,413	4,413
		30201600	FLY ASH	TON	110	110
	*	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	3,700	3,700
		40600300	AGGREGATE (PRIME COAT)	TON	10	10
	*	40600995	TEMPORARY RAMP, SPECIAL	SQ YD	100	100
		40603080	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N50	TON	1,340	1,340
		40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	200	200
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	380	380
	*	44000100	PAVEMENT REMOVAL	SQ YD	720	720
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	16	16
	*	44004500	PAVEMENT REMOVAL (SURFACE COURSE)	SQ YD	842	842
	*	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	390	390
		48203100	HOT-MIX ASPHALT SHOULDERS	TON	280	280
	*	50105220	PIPE CULVERT REMOVAL	FOOT	30	30
	*	54213453	END SECTIONS 18"	EACH	6	6
		54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3
		54215418	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 18"	EACH	1	1
	*	54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	3	3
		542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	165	165
	*	542C0223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	510	510
	*	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	123	123
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2
	*	60603300	GUTTER OUTLET	EACH	2	2
		67100100	MOBILIZATION	L SUM	1	1
	*	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
	*	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
	*	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	603	603

FILE NAME: P:\CIBEL WEST Projects\2009\97-0244 Lindgren Rd\Civil\Drawn\Sheet\500.dwg



USER NAME = #USER#	DESIGNED - KMA	REVISED -
PLOT SCALE = NONE	DRAWN - NDP	REVISED -
PLOT DATE = 10/28/2009	CHECKED - SBP	REVISED -
	DATE - 10/1/09	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
1 OF 2**

SCALE: NONE SHEET NO. 4 OF 54 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	09-00068-00-FP	DEKALB	54	4
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT			CONTRACT NO. 87406	