

LANDSCAPING AND EROSION CONTROL

CODE NO.	PAY ITEM DESCRIPTION	UNIT	LINDGREN RD. STA. 35+66.76 TO STA. 41+69.59	PLANK RD. STA. 294+20.86 TO STA. 302+01.07	NATIONAL ST. STA. 1+80 TO STA. 5+00	EX. LINDGREN RD. STA. 24+13.29 TO STA. 32+00
25000210	SEEDING, CLASS 2A	ACRE	0.7	0.4	0.3	0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	64	36	27	44
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	64	36	27	44
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	64	36	27	44
25100630	EROSION CONTROL BLANKET	SQ YD	4092	2040	1530	2560
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	160	80	60	100
28000400	PERIMETER EROSION BARRIER	FOOT	0	370	240	940
28000500	INLET AND PIPE PROTECTION	EACH	4	0	1	1
X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	12	7	7	9

PAVEMENT

CODE NO.	PAY ITEM DESCRIPTION	UNIT	LINDGREN RD. STA. 35+66.76 TO STA. 41+69.59	PLANK RD. STA. 294+20.86 TO STA. 302+01.07	NATIONAL ST. STA. 1+80 TO STA. 5+00	EX. LINDGREN RD. STA. 24+13.29 TO STA. 32+00
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	3085	0	1328	0
30201600	FLY ASH	TON	75	0	35	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1400	1300	1000	0
40600300	AGGREGATE (PRIME COAT)	TON	4	3	3	0
40600995	TEMPORARY RAMP, SPECIAL	SQ YD	0	73	16	11
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	427	588	325	0
40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	0	200	0	0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	215	0	165	0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	242	0	148	0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	85	140	55	0
XX006846	AGGREGATE FIELD ENTRANCE	SQ YD	113	0	0	56
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2370	2155	1765	0

PAVEMENT MARKINGS AND SIGNAGE

CODE NO.	PAY ITEM DESCRIPTION	UNIT	LINDGREN RD. STA. 35+66.76 TO STA. 41+69.59	PLANK RD. STA. 294+20.86 TO STA. 302+01.07	NATIONAL ST. STA. 1+80 TO STA. 5+00	EX. LINDGREN RD. STA. 24+13.29 TO STA. 32+00
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	0	73	0	0
70300625	TEMPORARY PAINT PAVEMENT MARKING, LINE 4"	FOOT	0	588	2138	3970
70300635	TEMPORARY PAINT PAVEMENT MARKING, LINE 6"	FOOT	0	934	0	0
70300645	TEMPORARY PAINT PAVEMENT MARKING, LINE 12"	FOOT	0	84	0	0
70300660	TEMPORARY PAINT PAVEMENT MARKING, LINE 24"	FOOT	24	32	0	12
72000100	SIGN PANEL - TYPE 1	SQ FT	62	27	34	33
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	195	0	60	128
73000100	WOOD SIGN SUPPORT	FOOT	0	30	0	0
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36	73	0	0
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2789	2905	761	129
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	413	57	0	0
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	0	769	0	0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	146	81	0	0
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	37	0	0	0
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36	0	0	0
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	389	0	0	2168
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	128	0	0	0
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	28	0	0	21
XX005938	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	0	0	0	2

NOTE: NORTH GROVE ROAD QUANTITIES HAVE BEEN INCLUDED IN LINDGREN ROAD STA. 36+68.76 TO STA. 41+69.59.

DRAINAGE ITEMS

CODE NO.	PAY ITEM DESCRIPTION	UNIT	LINDGREN RD. STA. 35+66.76 TO STA. 41+69.59	PLANK RD. STA. 294+20.86 TO STA. 302+01.07	NATIONAL ST. STA. 1+80 TO STA. 5+00	EX. LINDGREN RD. STA. 24+13.29 TO STA. 32+00
20800150	TRENCH BACKFILL	CU YD	80	0	20	14
21400100	GRADING AND SHAPING DITCHES	FOOT	1175	0	0	1069
28100105	STONE RIPRAP, CLASS A3	SQ YD	58	0	29	13
54213453	END SECTIONS 18"	EACH	2	0	2	2
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	0	0	0
54215418	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 18"	EACH	1	0	0	0
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	3	0	0	0
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	165	0	0	0
542C0223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	378	0	96	36
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	123	0	0	0
60218400	MANHOLES, TY A, 4'-DIA, TYPE 1 FRAME, CLOSED LID	EACH	2	0	0	0
60603300	GUTTER OUTLET	EACH	0	0	2	0

REMOVAL ITEMS

CODE NO.	PAY ITEM DESCRIPTION	UNIT	LINDGREN RD. STA. 35+66.76 TO STA. 41+69.59	PLANK RD. STA. 294+20.86 TO STA. 302+01.07	NATIONAL ST. STA. 1+80 TO STA. 5+00	EX. LINDGREN RD. STA. 24+13.29 TO STA. 32+00
44000100	PAVEMENT REMOVAL	SQ YD	0	89	0	631
44004500	PAVEMENT REMOVAL (SURFACE COURSE)	SQ YD	0	0	0	842
50105220	PIPE CULVERT REMOVAL	FOOT	0	0	0	30
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	0	0	0	2

FILE NAME = P:\DBBEL WEST Projects\2009\09-00104 Lindgren_Rd\Drawings\SCHEDULE E.dwg



USER NAME = #USER#
PLOT SCALE = NONE
PLOT DATE = 10/28/2009

DESIGNED - KMA
DRAWN - NDP
CHECKED - SBP
DATE - 10/1/09

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 10 OF 54 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	09-00068-00-FP	DEKALB	54	10
FED. ROAD DIST. NO. 3 [ILLINOIS] FED. AID PROJECT				

CONTRACT NO. 87406