

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL	STRUCTURE NO. 053-5014		STRUCTURE NO. 053-5015	
				ROADWAY 1000	STRUCTURE X028-2A	ROADWAY 1000	STRUCTURE X028-2A
20100110	TREE REMOVAL (6 TO 15 UNIT DIAMETER)	UNIT	44			44	
* 20200100	EARTH EXCAVATION	CU YD	563	236		327	
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	339		228		111
20700220	POROUS GRANULAR EMBANKMENT	CU YD	660	360		300	
* 20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	334		226		108
* 21300010	EXPLORATION TRENCH, SPECIAL	FOOT	400	200		200	
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5	0.2		0.3	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SO YD	2530	1090		1440	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	740	310		430	
28000305	TEMPORARY DITCH CHECKS	FOOT	140	80		60	
28000400	PERIMETER EROSION BARRIER	FOOT	1509	768		741	
28100109	STONE RIPRAP, CLASS A5	SO YD	1185		480		705
35100100	AGGREGATE BASE COURSE, TYPE A	TON	430	230		200	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	390	180		210	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	210	110		100	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	85	40		45	
44000100	PAVEMENT REMOVAL	SO YD	570	310		260	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	370	130		240	
44004000	PAVED DITCH REMOVAL	FOOT	407		152		255
48100100	AGGREGATE SHOULDERS, TYPE A	TON	570	340		230	
* 50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1		
* 50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1

\* SPECIAL PROVISION

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL	STRUCTURE NO. 053-5014		STRUCTURE NO. 053-5015	
				ROADWAY 1000	STRUCTURE X028-2A	ROADWAY 1000	STRUCTURE X028-2A
50800105	REINFORCEMENT BARS	POUND	92,090		50,740		41,350
△ 50901050	STEEL RAILING, TYPE SM	FOOT	140		74		66
51500100	NAME PLATES	EACH	2		1		1
54003000	CONCRETE BOX CULVERTS	CU YD	396.9		227.7		169.2
* 54248515	CONCRETE COLLAR	EACH	1	1			
* 61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	1	1			
* 61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	1	1			
* 61140000	STORM SEWERS, SPECIAL 8"	FOOT	40	40			
* 61140900	STORM SEWERS, SPECIAL 24"	FOOT	107	107			
* 61141300	STORM SEWERS, SPECIAL 36"	FOOT	86	86			
△ 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	25			25	
△* 63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	400	200		200	
△* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8	4		4	
△ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2			
* 63200310	GUARDRAIL REMOVAL	FOOT	859	437		422	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	10	6		4	
67100100	MOBILIZATION	L SUM	1	0.5		0.5	
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	0.5		0.5	
△* 78200455	BIDIRECTIONAL GUARD RAIL REFLECTORS	EACH	18	10		8	
△* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2			
* X0322208	TEMPORARY STORM SEWER PLUGS	EACH	1	1			

\* SPECIAL PROVISION  
△ SPECIALTY ITEMS

DESIGNED - JML	REVISED -
DRAWN - DJM	REVISED -
CHECKED - MSW	REVISED -
DATE - 10/21/09	REVISED -

LIVINGSTON COUNTY DEPARTMENT OF HIGHWAYS

SUMMARY OF QUANTITIES

WESTON ROAD (C.H. 10) OVER HICKORY CREEK  
SECTION 09-00120-03-BR  
LIVINGSTON, COUNTY

F.A.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	09-00120-03-BR	LIVINGSTON	34	3
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		CONTRACT NO. 87412		

SCALE: SHEET NO. 3 OF 34 SHEETS STA. TO STA.

FARNSWORTH GROUP, INC.

CONSULTING ENGINEERS - 2709 MCGRAW DRIVE BLOOMINGTON, ILLINOIS 61704 (309) 663-8435 / (309) 663-1571 FAX

24-8255