

SUMMARY OF QUANTITIES

	PAY ITEM	DESCRIPTION	UNIT	CONSTRUCTION CODE TYPE 1000 QUANTITY
	20200100	EARTH EXCAVATION	CU. YD.	1114
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU. YD.	525
*	20400800	FURNISHED EXCAVATION	CU. YD.	1037
	20800150	TRENCH BACKFILL	CU. YD.	226
	25000210	SEEDING CLASS 2A	ACRE	1
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90
	25100630	EROSION CONTROL BLANKET	SQ. YD.	418
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	333
	28000400	PERIMETER EROSION BARRIER	FOOT	1726
	28000500	INLET AND PIPE PROTECTION	EACH	17
	31100900	SUB-BASE GRANULAR MATERIAL, TYPE A 10"	SQ. YD.	294
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ. YD.	674
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.9
	40600300	AGGREGATE (PRIME COAT)	TON	14
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	300
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	698
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1234
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ. FT.	5664
	42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ. FT.	399
	42400800	DETECTABLE WARNINGS	SQ. FT.	40
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ. YD.	1561
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ. YD.	321
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	251
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ. YD.	13
	44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ. YD.	14
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3391
	48100100	AGGREGATE SHOULDERS, TYPE A	TON	496
	50105220	PIPE CULVERT REMOVAL	FOOT	209
	54213447	END SECTIONS 12"	EACH	1
	55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	207
	55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	100
	55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	262
	55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	99
*	550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	108
*	550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	41
*	550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	180
*	60107700	PIPE UNDERDRAINS 6"	FOOT	50
	60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	4
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1
*	60213200	CATCH BASINS (RECTANGULAR), SPECIAL WITH SPECIAL FRAME AND GRATE	EACH	9
	60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
	60219300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	1
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1
	60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	1
*	60603400	GUTTER OUTLET (SPECIAL)	EACH	4
*	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2100
	67100100	MOBILIZATION	L.SUM	1
*	70101700	TRAFFIC CONTROL AND PROTECTION	L.SUM	1
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6287
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	1692
	72000100	SIGN PANEL - TYPE 1	SQ. FT.	58.5
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	90
	73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	7
Δ	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ. FT.	62.4
Δ	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8780
Δ	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	354
Δ	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	427
Δ	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	209
*	X0712400	TEMPORARY PAVEMENT	SQ. YD.	889
*	Z0001050	AGGREGATE SUBGRADE 12"	SQ. YD.	2262
*	Z0013798	CONSTRUCTION LAYOUT	L.SUM	1
Δ	XX004914	TEMPORARY TRAFFIC SIGNAL SYSTEM	EACH	5
*		SEE SPECIAL PROVISIONS		
Δ		SPECIALTY ITEMS		

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5370	*	DEKALB	35	3
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-	
* Section 09-00175-00-SP			Contract #87419	

SUMMARY OF QUANTITIES

DRESSER & NORMAL ROADS
SECTION 09-00175-00-SP
CITY OF DEKALB

wendler

www.wendlers.com

GROUND BREAKING SOLUTIONS
engineers - surveyors - scientists

ph: 815.288.2281

Date:
10/22/2009

Job:
2098003