

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	PAY ITEM	UNIT	QUAN	SFTY-1B	
* 20200410	EARTH EXCAVATION (SPECIAL)	CU YD	144	144	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	961	961	
* 25200650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	961	961	
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8534	8534	
42400800	DETECTABLE WARNINGS	SQ FT	776	776	
44000100	PAVEMENT REMOVAL	SQ YD	25	25	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	80	80	
44000600	SIDEWALK REMOVAL	SQ FT	2690	2690	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	80	80	
67100100	MOBILIZATION	L SUM	1	1	
* 70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	

GENERAL NOTES:

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES BY LIMITING CURB AND GUTTER REPAIR TO ONE-HALF THE DRIVEWAY WIDTH AT ONE TIME AS WELL AS TEMPORARY AGGREGATE.
- WHERE CURB IS NOT PRESENT, THE LAST 5' OF NEW WALK SHALL BE THICKENED TO A MINIMUM OF 7". THIS WORK SHALL BE CONSIDERED INCIDENTAL TO PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH.

* - INDICATES SPECIAL PROVISION

△ - INDICATES SPECIALTY ITEMS

FILE NAME = 09471-QUAN-01 - P01

USER NAME =	DESIGNED -- BRIAN D. BROWN	REVISED -- IDOT REVIEW 10-09-09
	CHECKED -- BRIAN D. BROWN	REVISED --
PLOT SCALE =	DRAWN -- JRA	REVISED --
PLOT DATE = 10/21/09	CHECKED -- BDB	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ADA SIDEWALK IMPROVEMENTS
VARIOUS LOCATIONS WITHIN COAL CITY
SUMMARY OF QUANTITIES AND GENERAL NOTES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	09-00029-00-SW	GRUNDY/ WILL	5	2
CONTRACT NO. 87437				
SCALE: NONE SHEET NO. 2 OF 5 SHEETS STA. TO STA. FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003(498)				