

STA. 0+01 TO STA. 20+25

HOT-MIX ASPHALT SURFACE REMOVAL (COLD MILLING), 2" = 10,635.4 S.Y.  
 BITUMINOUS MATERIALS (PRIME COAT) = 924 GALLONS  
 AGGREGATE (PRIME COAT) = 10.9 TONS  
 LEVEL BINDER (MACHINE METHOD), N50, 3/4" = 448.7 TONS  
 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50, 1-1/4" = 764.5 TONS

FA.U. ROUTE NO.	SECTION	ILLINOIS PROJECT	CONTRACT NO.	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIES	09-00162-00-RS	ARA-5052 (026)	87439	LASALLE	9	4

STA. 0+01 TO STA. 1+29 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 257 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 104 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (SMALL) = 47 S.F.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (SMALL) = 47 S.F. OF PAVEMENT MARKING REMOVAL INCIDENTAL TO THERMOPLASTIC PAVEMENT MARKING

STA. 1+22 - RT. & LT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 21.1 S.Y. (5' X 38')

STA. 1+65 - 41.5' LT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 13.3 S.Y. (5' X 24')

STA. 1+93 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 97 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 23 FT.

STA. 2+00 - LT. TO STA. 3+28 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 257 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 104 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (SMALL) = 47 S.F.

STA. 7+99 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 97 FT.

STA. 6+64 TO STA. 7+92 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 257 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 104 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 28 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (SMALL) = 47 S.F.

STA. 8+25 - 43.5' LT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 17.8 S.Y. (5' X 32')

STA. 8+55 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 90 FT.

STA. 8+62 TO STA. 9+90 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 257 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 104 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 28 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (SMALL) = 47 S.F.

STA. 10+26 - RT. TO STA. 11+51 - RT.  
 RAILROAD CROSSING  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 125 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 66 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (LARGE) = 61.2 S.F.

STA. 10+19 - RT. TO STA. 11+00 - RT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING), 1-1/4" = 9.0 S.Y. (8' X 1')

STA. 8+25 - RT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 57 FT.

STA. 8+25 - 39.5' RT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 15.3 S.Y. (5' X 27.5')

STA. 5+51 - RT. TO STA. 6+00 - RT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING), 1-1/4" = 5.4 S.Y. (49' X 1')

STA. 3+28 TO STA. 6+64  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 80 FT.

STA. 1+65 - 54.5' RT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 13.3 S.Y. (5' X 24')

STA. 1+65 - RT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 55 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 14 FT.

STA. 1+35 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 76 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 21 FT.

STA. 15+35 - LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 10 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 108 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 23 FT.

STA. 15+35 - 56.5' LT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 21.9 S.Y. (5' X 39.5')

STA. 17+86 TO STA. 19+14 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 257 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 104 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (SMALL) = 47 S.F.

STA. 18+95 - RT. & LT. TO STA. 19+25 - RT. & LT.  
 DETECTOR LOOP REPLACEMENT (14 GA.) = 107 FT.

STA. 19+55 - 33.5' LT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 27.2 S.Y. (5' X 49')

STA. 19+87 - RT./LT. TO STA. 20+25 - RT./LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 38 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 118 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" YELLOW = 52 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 20 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS = 28.6 S.F.

STA. 19+75 - RT. & LT. TO STA. 20+17 - RT. & LT.  
 DETECTOR LOOP REPLACEMENT (14 GA.) = 95 FT.

STA. 20+25 - RT. & LT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 25.0 S.Y. (5' X 45')

STA. 19+55 - 31.0' RT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 27.8 S.Y. (5' X 50')

STA. 11+75 - 32.0' LT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 7.8 S.Y. (5' X 14')

STA. 11+87 - C  
 MANHOLE FRAME TO BE ADJUSTED W/NEW TY. 1 FR. & C.L.

STA. 14+21 - RT. TO STA. 15+01 - RT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 160 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 80 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 24 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (SMALL) = 47 S.F.

STA. 15+78 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 96 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 23 FT.

STA. 16+98 - LT. TO STA. 17+38 - LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 28 FT.

STA. 18+26 - LT. TO STA. 18+98 - LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 38 FT.

STA. 11+50 - RT. & LT.  
 SAW CUT BUTT JOINT, 2"

STA. 10+85

WALKER STREET

CLAY STREET

STREET

STILLMORE STREET

STREET

CLINTON STREET

CANAL

STA. 9+90 TO STA. 14+21 - C  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 100 FT.

STA. 12+57 - RT. TO STA. 12+99 - RT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING), 1-1/4" = 4.7 S.Y. (42' X 1')

STA. 15+08 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 116 FT.

STA. 11+61 - LT. TO STA. 12+91 - LT.  
 RAILROAD CROSSING  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 125 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 66 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (LARGE) = 61.2 S.F.

STA. 11+60 - RT. & LT.  
 SAW CUT BUTT JOINT, 2"

STA. 11+75 - 40.0' RT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 9.4 S.Y. (5' X 17')

STA. 11+40 - 33.0' RT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 10 S.Y. (5' X 18')

STA. 15+40 - RT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 97 FT.

STA. 15+40 - 43.5' RT.  
 SAW CUT BUTT JOINT, 1-1/4"  
 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT, 1-1/4"-2", 26.7 S.Y. (5' X 48')

STA. 15+85 - C TO STA. 17+86 - C  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" YELLOW = 50 FT.

STA. 17+92 - RT. TO STA. 18+98 - RT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 4" WHITE = 46 FT.

STA. 19+22 - RT. & LT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 6" WHITE = 94 FT.  
 THERMOPLASTIC PAVEMENT MARKING - LINE, 24" WHITE = 28 FT.

**RENWICK & ASSOCIATES, INC.**

228 West Main Street  
 Ottawa, Illinois 61350  
 TEL: 815-434-3200  
 FAX: 815-434-3968

