

SCHEDULE OF QUANTITIES

PAVEMENT REMOVAL SCHEDULE				PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING), VARIABLE DEPTH
LOCATION				SQ YD	SQ YD	SQ YD
STA. 46+70.00	TO	STA. 47+00.00		133.5		
STA. 47+00.00	TO	STA. 64+70.00				2,474.0
SANTA FE	LT				45.6	
SANTA FE	RT				70.0	
LOGAN	LT				35.3	
SEVENTH	RT				36.8	
FINNEY	LT				35.3	
SIXTH	RT				39.7	
FIFTH	LT				35.4	
FIFTH	RT				44.7	
STA. 64+70.00	TO	STA. 65+00.00		133.5		
TOTAL				267	343	2,474

MOBILIZATION	
LOCATION	L. SUM
ENTIRE PROJECT	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION	
LOCATION	L. SUM
ENTIRE PROJECT	1
TOTAL	1

ROAD SURFACE SCHEDULE							
LOCATION		AREA FOR INFORMATION ONLY	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	LEVELING BINDER (HAND METHOD) N30	POLYMERIZED HMA SURFACE COURSE MIX D, N70
		SQ YD	TON	TON	TON	TON	TON
STA. 46+70.00	TO	STA. 65+00.00	8,133.0	814.0	9.87		910.9
SANTA FE (NORTH)			291.0	29.0	0.35		32.6
SANTA FE (SOUTH)			412.0	42.0	0.50		46.1
LOGAN			154.0	16.0	0.19		17.2
SEVENTH			192.0	19.0	0.23		21.5
FINNEY			152.0	15.0	0.18		17.0
SIXTH			209.0	21.0	0.25		23.4
FIFTH (NORTH)			135.0	14.0	0.17		15.1
FIFTH (SOUTH)			195.0	20.0	0.24		21.8
VARIOUS LOCATIONS					8.0	8.0	
TOTAL		9,873.0	980.0	12.0	8.0	8.0	1,106

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL. DA.
ENTIRE PROJECT	11
TOTAL	11

CONSTRUCTING TEST STRIP	
LOCATION	EACH
ENTIRE PROJECT	1
TOTAL	1

THERMOPLASTIC PAVEMENT MARKING SCHEDULE				
PAVEMENT MARKING - LINE 4"				
PAVEMENT MARKING - LINE 24"				
YELLOW SKIP DASH				
WHITE				
FOOT				
FOOT				
STA. 46+70	TO	STA. 65+00	CL	458
SANTA FE		NORTH		26
SANTA FE		SOUTH		32
TRUITT		WEST		11
TRUITT		EAST		11
TOTAL				458
TOTAL				80

CONSTRUCTION LAYOUT	
LOCATION	L. SUM
ENTIRE PROJECT	1
TOTAL	1

TEMPORARY RAMP	
LOCATION	SQ YD
STA. 47+00	22.0
STA. 64+70	22.0
TOTAL	44.0

FILE NAME = L:\CHIL000\PLANS-XREFS\04-SCHED QTY.DGN
 USER NAME =
 DESIGNED -
 DRAWN -
 PLOT SCALE =
 CHECKED -
 PLOT DATE = 10-01-09

REVISOR -
 REVISED -
 REVISED -
 REVISED -
 DATE -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**CITY OF CHILICOTHE - TRUITT AVENUE
 SCHEDULE OF QUANTITIES**

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6548	09-00008-00-RS	PEORIA	12	4
CONTRACT NO. 89548				

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

ILLINOIS FED. AID PROJECT