

SUMMARY OF QUANTITIES

PAY ITEM CODE	DESCRIPTION	QUANTITY	UNIT
20100500	TREE REMOVAL, ACRES	0.40	ACRE
20200100	EARTH EXCAVATION	996	CU YD
20400800	FURNISHED EXCAVATION	2084	CU YD
25000200 *	SEEDING, CLASS 2	1.0	ACRE
25000310 *	SEEDING, CLASS 4	0.3	ACRE
25000400 *	NITROGEN FERTILIZER NUTRIENT	90	POUND
25000500 *	PHOSPHORUS FERTILIZER NUTRIENT	90	POUND
25000600 *	POTASSIUM FERTILIZER NUTRIENT	90	POUND
25100115 *	MULCH, METHOD 2	1.0	ACRE
25100120 *	MULCH, METHOD 2	1.0	TON
28000250 *	TEMPORARY EROSION CONTROL SEEDING	500	POUND
28000305	TEMPORARY DITCH CHECKS	90	FOOT
28000400	PERIMETER EROSION BARRIER	300	FOOT
28000500	INLET AND PIPE PROTECTION	7	EACH
35100100	AGGREGATE BASE COURSE, TYPE A	1360	TON
35101400	AGGREGATE BASE COURSE, TYPE B	731	TON
40300100	BITUMINOUS MATERIALS (PRIME COAT)	2278	GALLON
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	4434	GALLON
40300600	SEAL COAT AGGREGATE	178	TON
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	272	SQ FT

42400800	DETECTABLE WARNINGS	40	SQ FT
44000600	SIDEWALK REMOVAL	1988	SQ FT
542D0213	PIPE CULVERTS, CLASS D, TYPE 1 8"	64	FOOT
542D0215	PIPE CULVERTS, CLASS D, TYPE 1 10"	80	FOOT
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	32	FOOT
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	38	FOOT
542D1087	PIPE CULVERTS, CLASS D, TYPE 2 42"	36	FOOT
54215577	METAL END SECTIONS 42"	2	EACH
66400105	CHAIN LINK FENCE, 4'	195	FOOT
66400805	CHAIN LINK GATES, 4'X5' SINGLE	1	EACH
67100100	MOBILIZATION	1.0	L SUM
72000100	SIGN PANEL- TYPE 1	36	SQ FT
78001110 *	PAINT PAVEMENT MARKING - LINE 4"	500	FOOT
78001130 *	PAINT PAVEMENT MARKING - LINE 6"	52	FOOT
78001180 *	PAINT PAVEMENT MARKING - LINE 24"	13	FOOT
78001300 *	PAINT PAVEMENT MARKINGS- LETTERS AND SYMBOLS, APPLIED	9.2	SQ FT
A2001016 *	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	7	EACH
X0350800	BOLLARDS	2	EACH
XX001011	BICYCLE RACKS	2	EACH
XX008010	FITNESS EQUIPMENT COMPLETE	1	L. SUM
XX0301430	PRECAST CONCRETE PARKING BLOCK	17	EACH
XX006785	TIMBER BICYCLE RAILING	460	FOOT
XX008011	TIMBER RUB RAIL	400	FOOT
XX008012	WOODEN SIGN POST 4"X4"X10'	11	EACH
XX008013	WOODEN SIGN POST 4"X4"X12'	2	EACH
28100207	STONE RIPRAP, CLASS A-4	100	TON
28100208	STONE RIPRAP, CLASS A-4 (SPECIAL)	1128	TON
28200200	FILTER FABRIC	1801	SQ YD

* SPECIALTY ITEMS

UTILITIES

POWER & GAS: Ameren CIPS
 711 SOUTH 9TH STREET
 MATTOON ILLINOIS 61938

TELEPHONE: CONSOILDATED TELEPHONE COMPANY
 121 SOUTH 17TH STREET
 MATTOON ILLINOIS 61938

WATER & SEWER: CITY OF SHELBYVILLE ILLINOIS
 131 SOUTH MORGAN STREET
 SHELBYVILLE ILLINOIS 62565

INDEX OF PAGES

1. COVER SHEET
2. INDEX OF PAGES AND HIGHWAY STANDARDS, SUMMARY OF QUANTITIES AND UTILITIES
3. GENERAL NOTES & RATES OF APPLICATIONS
4. TYPICAL CROSS SECTIONS
5. TIMBER RAIL DETAILS
6. SIGN LOCATION PAGE
7. PARKING LOT DETAILS
8. SCHEDULES
9. PLAN SHEET
10. CURVE DETAILS & BENCHMARKS
- 11-13 PROFILE SHEETS
- 14-27 CROSS SECTION SHEETS

HIGHWAY STANDARDS	
STANDARD NUMBER	STANDARD NAME
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
424001-05	CURB RAMPS FOR SIDEWALK
542401-01	METAL END SECTION FOR PIPE CULVERT
664001-02	CHAIN LINK FENCE
701801-04	LANE CLOSURE + CROSSWALK AN SIDEWALK CLOUSRES
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
BLR - 21-8	TRAFFIC CONTROL DEVICES ON RURAL LOCAL HIGHWAYS

CITY OF SHELBYVILLE ILLINOIS
 GENERAL DACEY TRAIL
 PHASE 4