

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	08-00048-00-BT	SHELBY	27	8

\*\* GENERAL DACEY TRAIL

**BOLLARDS**

STA	O/S	QUANTITY
410+39	C.L.	1.0 EACH
410+67	C.L.	1.0 EACH
	<b>TOTAL</b>	<b>2.0 EACH</b>

**PAINT PAVEMENT LINE 6"**

STA TO STA	OFFSET	COLOR	QUANTITY
410 + 40 TO 410+66	11' LEFT	WHITE	26 FOOT
410 + 40 TO 410+66	11' RIGHT	WHITE	26 FOOT
		<b>TOTAL</b>	<b>52 FOOT</b>

**PAINT PAVEMENT LINE 24"**

STA TO STA	OFFSET	COLOR	QUANTITY
410+40 TO 410+53	14' LEFT	WHITE	13 FOOT
		<b>TOTAL</b>	<b>13 FOOT</b>

**SIDEWALK REMOVAL SCHEDULE**

LOCATIONS	WIDTH	QUANTITY
STA 52+80 TO STA 55+00	4.0	888 SQ. FT.
STA 440+00 TO STA 442+75	4.0	1100 SQ. FT.
	<b>TOTAL</b>	<b>1988 SQ. FT.</b>

**PORTLAND CEMENT CONCRETE  
SIDEWALK 5" SCHEDULE**

STA TO STA	WIDTH	SQ FT
STA 410+40 TO 410+38	10	20
STA 410+36 TO 410+26	10	100
STA 410+66 TO 410+68	10	20
STA 410+70 TO 410+80	10	100
STA 55+10 TO 55+14	8	32
	<b>TOTAL</b>	<b>272</b>

**PIPE CULVERT SCHEDULE**

SIZE	TYPE	LOCATION	LENGTH	METAL END SECTIONS
8"	1	433+00	32 FOOT	0
8"	1	435+20	32 FOOT	0
10"	1	1+98	32 FOOT	0
10"	1	401+00	24 FOOT	0
10"	1	410+28	24 FOOT	0
15"	1	410+95	32 FOOT	0
24"	2	419+61	38 FOOT	0
42"	2	405+80	36 FOOT	2

**DETECTABLE WARNINGS**

STA TO STA	WIDTH	SQ. FT.
410+38 TO 410+36	10	20
410+68 TO 410+70	10	20
	<b>TOTAL</b>	<b>40 SQ. FT.</b>

CITY OF SHELBYVILLE ILLINOIS  
GENERAL DACEY TRAIL  
PHASE 4