

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION		CHANNEL EXCAVATION		ESTIMATED UNSUITABLE MATERIAL		SUITABLE MATERIAL ADJUSTED FOR SHRINKAGE		EMBANKMENT		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STA 0+00 TO 4+74.3	76.6	0.0	0.0	0.0	0.0	57.5	143.2	143.2	0.0	0.0	-85.7	
STA 4+74.3 TO 5+25.7	0.0	95.0	0.0	0.0	47.5	35.6	0.0	0.0	0.0	0.0	35.6	
STA 5+25.7 TO 10+00	70.8	0.0	0.0	0.0	0.0	53.1	71.6	71.6	0.0	0.0	-18.5	
1 FIELD ENTRANCE	0.0	0.0	0.0	0.0	0.0	0.0	3.2	3.2	0.0	0.0	-3.2	
TOTAL	147.4	95.0	0.0	0.0	47.5	146.2	218.0	218.0	0.0	0.0	-71.8	


C.H.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4	07-00064-00-BR	EDWARDS	13	3
FED. ROAD DIST. NO. 7 ILLINOIS		FED. AID PROJECT		
PROJECT# ARA-047(032)		CONTRACT# 95606		
JOB NO. C-97-023-10		BEAR CREEK		

323 W. 3RD ST.
P.O. BOX 160
MT. CARMEL, IL
62863
PHONE:
(618)-262-8651
FAX:
(618)-263-3327

405 W. STATE ST
SUITE 1
PRINCETON, IN
47670
PHONE:
(812)-386-7611
FAX:
(812)-385-2812



PROFESSIONAL DESIGN FIRM
LAND SURVEY &
ENGINEERING
CORPORATION
184-000887
(82-032435)(35-002769)



AARON M. MEFFORD
NAME
Aaron Mefford
SIGNATURE
10-26-09
DATE
113011
EXPIRES

BEAR CREEK
COUNTY HIGHWAY 4
EDWARDS COUNTY, ILLINOIS

SHEET TITLE:

CROSS-SECTIONS

SCALE: 1" = 5'
BY: AMM
DATE: 10/20/09
REV:

3 OF 13
SHEETS

SHEET NO.
3