

F.A.S. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
748	06-00053-00 RS	JERSEY	110	10
STA. NA		TO STA. NA		
CONTRACT #97375		PROJECT NO. RS-0748(109)		

PROPOSED SIGN SCHEDULE										
ROADWAY	LOCATION	SIGN	METAL POST	WOOD POST	TELESCOPING STEEL SIGN SUPPORT	SIGN PANEL	RELOCATE SIGN PANEL	SIGN PANEL ASSEMBLY *	RELOCATE SIGN PANEL ASSEMBLY	
			TYPE A (FEET)	(FEET)	(FEET)	TYPE 1 (SQ FT)	TYPE 1 (SQ FT)	TYPE A (SQ FT)	TYPE A (SQ FT)	TYPE B (SQ FT)
Delhi Road	158+58, 49' LT	R1-1		13.8		6.25				
Delhi Road	158+83, 23' RT	W1-7		15		8				
Delhi Road	159+65, 52' LT								8	
Delhi Road	172+28, 61' RT	R1-1		14.3		6.25				
Delhi Road	172+39, 35' RT	D3			12.2					11
Delhi Road	233+50, 30' RT	D3		13.6			3			
Delhi Road	238+00, 32' LT	D3			9.5					14
Delhi Road	238+10, 43' LT	R1-1		11.8		6.25				
Delhi Road	241+69, 25' LT	W2-2, W16-8		11.3				8.25		
Delhi Road	242+02, 25' RT	W1-4, W13-1(45)		11.8				8.5		
Delhi Road	250+00, 17' LT	W1-8	11.4			3				
Delhi Road	250+90, 17' LT	W1-8, W1-8	11.3					6		
Delhi Road	251+80, 18' LT	W1-8, W1-8	11.5					6		
Delhi Road	252+70, 18' LT	W1-8, W1-8	11.5					6		
Delhi Road	253+60, 18' LT	W1-8, W1-8	11.5					6		
Delhi Road	254+50, 18' LT	W1-8, W1-8	11.5					6		
Delhi Road	255+40, 18' LT	W1-8, W1-8	11.5					6		
Delhi Road	256+30, 18' LT	W1-8, W1-8	11.6					6		
Delhi Road	257+10, 18' LT	W1-8	11.75			3				
Delhi Road	261+70, 18' RT	W1-8	11.7			3				
Delhi Road	262+60, 18' RT	W1-8, W1-8	11.5					6		
Delhi Road	263+50, 18' RT	W1-8, W1-8	11.5					6		
Delhi Road	264+40, 18' RT	W1-8, W1-8	11.75					6		
Delhi Road	265+30, 18' RT	W1-8, W1-8	11.5					6		
Delhi Road	266+02, 35' RT	R1-1		14.5		6.25				
Delhi Road	266+12, 25' RT	D3			11					10
Delhi Road	266+30' 18' RT	W1-8, W1-8	11					6		
Delhi Road	267+20, 18' RT	W1-8, W1-8	11.25					6		
Delhi Road	268+10, 18' RT	W1-8, W1-8	11.5					6		
Delhi Road	269+00, 18' RT	W1-8, W1-8	11.5					6		
Delhi Road	269+90, 18' RT	W1-8	11.7			3				
Delhi Road	271+27, 26' LT	W1-4, W13-1(45)		15.5				8.5		
Delhi Road	283+99, 61' LT	R1-1, W4-4P		14.6				8.25		
Delhi Road	284+42, 62' RT	R1-1, W4-4P		11.8				8.25		
Delhi Road	284+53, 35' RT	D3			12.1					12
Delhi Road	285+02, 25' RT	R2-1		15		5				
TOTAL			218.45	163	44.8	45	8	131.75	8	47

* Sign panel assembly will be paid for at the contract unit price per square foot for "SIGN PANEL".

MAILBOX RELOCATIONS	
STATIONS	
EXISTING	PROPOSED
172+40, LT	172+06, LT
187+57, LT	187+59, LT
191+75, LT	191+36, LT
193+60, LT	193+60, LT
193+62, LT	193+62, LT
196+44, LT	196+14, LT
201+37, LT	201+03, LT
209+81, LT	209+81, LT
209+83, LT	209+83, LT
212+00, LT	211+60, LT
229+72, LT	229+68, LT
229+74, LT	229+70, LT
253+16, LT	252+93, LT
261+46, LT	261+48, LT
264+14, RT	264+06, RT
273+45, LT	273+10, LT
275+87, LT	275+32, LT
276+21, LT	275+91, LT
276+74, LT	276+47, LT
278+45, LT	278+41, LT
279+34, RT	279+74, RT

REVISIONS	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

DELHI ROAD
F.A.S. ROUTE 748
SECTION 06-00053-00-RS
JERSEY COUNTY