

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	IL 156	Maeystown Rd
20200100	EARTH EXCAVATION	CU YD	485	195	290
25000100	SEEDING, CLASS 1	ACRE	0.5	0.1	0.4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	9	36
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	9	36
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	9	36
25100115	MULCH, METHOD 2	ACRE	0.5	0.1	0.4
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	71	3	68
28000400	PERIMETER EROSION BARRIER	FOOT	663		663
28000500	INLET AND PIPE PROTECTION	EACH	2		2
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	25		25
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	86	86	
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	1056	225	831
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	8		8
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	286	53	233
40600300	AGGREGATE (PRIME COAT)	TON	12	1.5	10.5
40600990	TEMPORARY RAMP	SQ YD	27	18	9
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	396	67	329
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	508	65	443
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	223	184	39
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	14	14	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	711	711	
42400800	DETECTABLE WARNINGS	SQ FT	20	20	
44000100	PAVEMENT REMOVAL	SQ YD	344	60	284
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1622	460	1162
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	214	18	196
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	130	89	41
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	316	66	250
44000600	SIDEWALK REMOVAL	SQ FT	50	50	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	499	345	154
44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	2300		2300
48101200	AGGREGATE SHOULDERS, TYPE B	TON	51		51
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	228	120	106
54213447	END SECTIONS 12"	EACH	2		2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	39		39
55100500	STORM SEWER REMOVAL 12"	FOOT	51		51
60238800	INLETS, TYPE A	EACH	2		2
60404300	FRAMES AND GRATES, TYPE 3	EACH	2		2
60500060	REMOVING INLETS	EACH	2		2
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	364		364
67100100	MOBILIZATION	L SUM	1	0.2	0.8
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0.2	0.8
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	384	150	234
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94		94
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5199	1530	3669
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	159		159
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	73	38	35
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2065	586	1479
72000100	SIGN PANEL - TYPE 1	SQ FT	4.0		4.0
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	5.0	5.0	
73000100	WOOD SIGN SUPPORT	FOOT	28	14	14
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94		94
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5199	1530	3669

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	IL 156	Maeystown Rd
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	159		159
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	73	38	35
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	27	9	18
78300100	PAVEMENT MARKING REMOVAL	SQ FT	60	60	

* SPECIALTY ITEMS

F.A.U. RTE.	SECTION	COUNTY
9314	08-00034-00-RS	MONROE

CONTRACT NO. 97403
FEDERAL AID PROJECT

SHEET NO.

3

Job No. 119-08-3

Date: 10/15/09

Scale: 1"=20'


Drawn by: BEC

Design by: BEC

Approved by: CMB

File Name: PLN

REVISIONS	5/27/08 RESURF IL 156
	7/30/08 REVISED SITE PLAN
	7/2/09 PLAN SPLIT
	10/28/09 QUANTITY CORRECTION



CBB Crawford, Bunte, Brammeier
Traffic and Transportation Engineers
St. Louis, Missouri / Glen Carbon, Illinois
314-878-6644 618-656-2612
Fax: 314-878-5876 E-Mail: cbb@cbtraffic.com

ROADWAY
SUMMARY OF QUANTITIES
MONROE COUNTY
IL 156 & MAEYSTOWN ROAD
WATERLOO, ILLINOIS