

TEMPORARY PAVEMENT MARKING SCHEDULE

(WESTBOUND IL 13)

STATION TO STATION	LOCATION	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING					SHORT TERM PAVEMENT MARKING	
			LINE 4"	LINE 4"	LINE 12"	LINE 24"	LETTERS & SYMBOLS WHITE		
			WHITE	YELLOW	WHITE	WHITE	SQ FT		
		SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	
WESTBOUND IL 13									
TERMINAL		ADDITIONAL QUANTITY FOR STAGING	107.7	215			18		
REDCO		ADDITIONAL QUANTITY FOR STAGING	241.3	400			54		
WB 630+50.0 TO 733+93.5		SHORT TERM QUANTITY						1354	
WB 630+50.0 TO 635+00.0		HATCHING IN FUTURE RIGHT TURN LANE	307.4			307.4			
WB 630+50.0 TO 733+93.5		SKIP-BETWEEN OUTSIDE AND CENTER LANES	862.0	2585.9					
WB 630+50.0 TO 733+93.5		REFRESH SKIP BETWEEN INSIDE AND CENTER LANES	862.0	2585.9					
WB 630+50.0 TO 660+27.6		RIGHT EDGE OF PAVEMENT	992.5	2977.6					
WB 630+67.8 TO 631+25.3		"ARROW"-RIGHT TURN LANE	20.7				20.7		
WB 632+57.7 TO 656+65.3		"ONLY"-RIGHT TURN LANE	15.8				15.8		
WB 635+72.7 TO 636+29.1		REFRESH LT EDGE OF PAVEMENT	802.5	2407.6			0.0		
WB 636+29.1 TO 691+40.0		"ARROW"-RIGHT TURN LANE	20.7				20.7		
WB 656+65.3 TO 660+71.5		"ONLY"-RIGHT TURN LANE	15.8				15.8		
WB 660+71.5 TO 660+93.5		LT EDGE OF PAVEMENT	0.0						
WB 660+63.5 TO 660+93.5		STOP BAR-RIGHT TURN LANE ON SB TERMINAL	36.0				18.0		
WB 660+88.4 TO 660+88.4		NW ISLAND	108.3	106.9		72.7			
WB 660+88.4 TO 660+99.0		"ARROW"-SB TERMINAL RIGHT TURN LANE	20.7				20.7		
WB 660+99.0 TO 660+99.0		"ONLY"-SB TERMINAL RIGHT TURN LANE	15.8				15.8		
WB 660+99.0 TO 660+81.5		"ARROW"-SB TERMINAL LEFT TURN LANE	20.7				20.7		
WB 660+81.5 TO 661+00.0		"ONLY"-SB TERMINAL LEFT TURN LANE	15.8				15.8		
WB 660+81.5 TO 661+00.0		SB TERMINAL RT EDGE OF PAVEMENT	74.4	223.3					
WB 661+00.0 TO 661+40.5		STOP BAR-SB TERMINAL LEFT TURN LANE	24.0				12.0		
WB 661+40.5 TO 660+93.5		STOP BAR-RIGHT TURN LANE	36.0				18.0		
WB 660+93.5 TO 661+05.5		SB TERMINAL BETWEEN RTL AND LTL	44.6	133.7					
WB 661+05.5 TO 661+50.6		LINE BETWEEN SB LTL AND NB LANE	51.9	0.0	155.7				
WB 661+50.6 TO 664+02.3		LINE BETWEEN RTL AND OUTSIDE THRU LANE	104.3	312.9					
WB 664+02.3 TO 664+60.3		"ARROW"-RIGHT TURN LANE	20.7				20.7		
WB 661+68.8 TO 707+68.4		"ONLY"-RIGHT TURN LANE	15.8				15.8		
WB 661+85.7 TO 666+35.2		RT EDGE OF PAVEMENT	1533.2	4599.6			0.0		
WB 666+35.2 TO 688+05.8		STOP BAR-THREE THRU LANES	72.0				36.0		
WB 670+60.5 TO 675+55.2		INSIDE EDGE OF PAVEMENT	149.8		449.5		0.0		
WB 675+55.2 TO 688+05.8		MEDIAN HATCHING	1104.2	1745.3		522.4	0.0		
WB 688+05.8 TO 691+40.0		RT EDGE OF ACCELERATION LANE	164.9	494.7			0.0		
WB 686+19.6 TO 687+38.7		RT EDGE OF DECELERATION LANE	93.7	281.2			0.0		
WB 687+38.7 TO 687+96.9		LT EDGE OF DECELERATION LANE	173.5		520.4		0.0		
WB 687+96.9 TO 691+40.0		"ARROW"-DECELERATION LANE	20.7				20.7		
WB 691+40.0 TO 708+25.0		"ONLY"-DECELERATION LANE	15.8				15.8		
WB 708+25.0 TO 708+13.5		REFRESH LT EDGE OF PAVEMENT	561.7		1685.0				
WB 708+13.5 TO 708+02.5		STOP BAR-REDCO RT TURN LANE	36.0				18.0		
WB 708+02.5 TO 708+51.2		NW ISLAND	124.6	174.6		66.4			
WB 708+51.2 TO 708+63.9		LINE BETWEEN REDCO SB THRU AND RT TURN LANE	25.3	76.0					
WB 708+63.9 TO 708+75.5		LINE BETWEEN REDCO SB THRU AND LT TURN LANE	25.3	76.0					
WB 708+75.5 TO 708+57.5		LINE BETWEEN REDCO NB THRU AND SB LT TURN LANE	25.0		75.0				
WB 708+57.5 TO 708+68.7		STOP BAR-SB REDCO THRU LANE	24.0				12.0		
WB 708+68.7 TO 708+93.3		STOP BAR-SB REDCO LT TURN LANE	24.0				12.0		
WB 708+93.3 TO 709+07.5		NE ISLAND	155.5	174.7		97.3			
WB 709+07.5 TO 711+51.5		STOP BAR-THREE THRU LANES	72.0				36.0		
WB 709+35.7 TO 733+93.5		REFRESH LINE BETWEEN INSIDE LANE AND OUTSIDE LTL	81.3		244.0				
WB 709+46.2 TO 712+65.0		REFRESH LT EDGE OF PAVEMENT	819.3		2457.8				
WB 709+50.2 TO 711+51.5		LINE BETWEEN RIGHT TURN LANE AND OUTSIDE THRU LANE	106.3	318.8					
WB 711+51.5 TO 710+25.8		STOP BAR-LEFT TURN LANES	50.0				25.0		
WB 710+25.8 TO 710+52.1		REFRESH LINE BETWEEN INSIDE AND OUTSIDE LEFT TURN LANES	67.1		201.3				
WB 710+52.1 TO 710+78.8		"ARROW"-RIGHT TURN LANE	20.7				20.7		
WB 710+78.8 TO 711+36.3		"ONLY"-RIGHT TURN LANE	15.8				15.8		
WB 711+36.3 TO 709+62.4		"ARROW"-LEFT TURN LANE	20.7				20.7		
WB 709+62.4 TO 733+93.5		"ARROW"-LEFT TURN LANE	20.7				20.7		
WB 733+93.5 TO 709+62.4		"ONLY"-LEFT TURN LANE	15.8				15.8		
WB 709+62.4 TO 733+93.5		"ONLY"-LEFT TURN LANE	15.8				15.8		
WB 709+62.4 TO 733+93.5		RT EDGE OF PAVEMENT	810.4	2431.1					
WB 709+62.4 TO 733+93.5		HATCHING	62.4			62.4			
SUBTOTALS			11345	19913	8196	1129	259	329	1354