



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 30, 2015

SUBJECT: FAP Route 318 (IL 29)  
Section [8R-1;(6,5)R]DM  
Peoria County  
Contract No. 68C87  
Item No. 11, January 15, 2016 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions
2. Added pages 57-59 to the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.  
Acting Bureau Chief of Design & Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" followed by "P.E." in smaller letters.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Kensil Garnett, Region 3, District 4; Tim Kell; Estimates

JW/kf

TABLE OF CONTENTS

LOCATION OF PROJECT ..... 1  
DESCRIPTION OF PROJECT ..... 1  
LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES ..... 1  
SEEDING, MINOR AREAS ..... 2  
BUILDING REMOVAL - CASE I (NON-FRIABLE AND FRIABLE ASBESTOS ABATEMENT)  
(BDE) ..... 2  
TRAFFIC CONTROL PLAN ..... 28  
RODENT EXTERMINATION ..... 28  
CONTRACT CLAIMS (BDE) ..... 29  
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) ..... 30  
EQUAL EMPLOYMENT OPPORTUNITY (BDE) ..... 41  
PROGRESS PAYMENTS (BDE) ..... 44  
SIDEWALK, CORNER, OR CROSSWALK CLOSURE (BDE) ..... 44  
TRACKING THE USE OF PESTICIDES (BDE) ..... 45  
WEEKLY DBE TRUCKING REPORTS (BDE) ..... 45  
WORKING DAYS (BDE) ..... 45  
VETERAN BUSINESS PROGRAM ..... 45  
ADDITIONAL BUILDING REMOVAL INFORMATION ..... 57

Revised 12/30/15

**ADDITIONAL BUILDING REMOVAL INFORMATION**

**SECTION 1**  
 1.2 Survey Summary & Results

**ACM SURVEY RESULTS - Parcel No. 4ADD001**  
**Single Family Residence**  
**1807 N. Fourth Street**  
**Chillicothe, Illinois 61523**

The following homogeneous building material types were sampled as part of this survey and their results are summarized in the table below:

MTL #	MATERIAL DESCRIPTION	LOCATION	F/NF <sup>1</sup>	COND. <sup>2</sup>	% ACM <sup>3</sup>	# SAMPLES	QUANTITY (ENG/MET)
01	Multi-layer vinyl sheet flooring/mastic – Type 1	Kitchen	NF	Good	Tile 5-10% Mastic ND	3	327 SF 30.4 SM
02	Window glazing	Exterior windows	NF	Fair	ND	3	100 LF 30.5 LM
03	Plaster	Throughout	NF	Fair	ND	7	5,500 SF 511.0 SM
04	Drywall/joint compound	Laundry room	NF	Fair	ND/ND	3	30 SF 2.8 SM
05	Wall board paper	Laundry room	NF	Fair	Fair	3	30 SF 2.8 SM
06	Multi-layer vinyl sheet flooring/mastic – Type 2	Bathroom	NF	Poor	Flooring 5-10% Mastic ND	3	27 SF 2.5 SM
07	Multi-layer vinyl sheet flooring/mastic – Type 3	Living room	NF	Fair	Flooring 5-10% Mastic ND	3	390 SF 36.2 SM
08	Multi-layer/multi-color vinyl sheet flooring/mastic	Bedroom 1	NF	Fair	ND/ND	3	100 SF 9.3 SM
09	Multi-layer/multi-color vinyl sheet flooring/mastic	Bedroom 3	NF	Fair	Flooring 5-10% Mastic ND	3	105 SF 9.8 SM
10	Multi-layer/multi-color vinyl sheet flooring/mastic	Laundry room	NF	Fair	ND/ND	3	100 SF 9.3 SM
11	Roofing shingles	House roof	NF	Good	ND	3	1,200 SF 111.5 SM
12	Roofing shingles	Garage roof	NF	Good	ND	3	650 SF 60.4 SM
13	12" x 12" multi-color vinyl floor tile/mastic	Trailer kitchen	NF	Fair	Flooring 5-10% Mastic ND	3	180 SF 16.7 SM

<sup>1</sup> F = Friable; NF = Nonfriable      Friability is further defined in section 4.  
<sup>2</sup> Cond. = Condition Of Materials      Either good, fair or poor.  
<sup>3</sup> ND = None Detected  
 \* Point Count Analysis

**SECTION 1**  
 1.2 Survey Summary & Results

**ACM SURVEY RESULTS - Parcel No. 4ADD001**  
**Single Family Residence**  
**1807 N. Fourth Street**  
**Chillicothe, Illinois 61523**

The following homogeneous building material types were sampled as part of this survey and their results are summarized in the table below:

MTL #	MATERIAL DESCRIPTION	LOCATION	F/NF <sup>1</sup>	COND. <sup>2</sup>	% ACM <sup>3</sup>	# SAMPLES	QUANTITY (ENG/MET)
14	12" x 12" white vinyl floor tile/mastic	Trailer bathroom	NF	Fair	ND/ND	3	50 SF 4.6 SM
15	Multi-layer vinyl sheet flooring/mastic	Bedroom	NF	Fair	ND	3	144 SF 13.4 SM
16	Paper board	Various locations throughout	NF	Poor	ND	3	350 SF 32.5 SM
17	Flat roofing material	Trailer roof	NF	Poor	1-5%	3	660 SF 61.3 SM
18	Roof flashing material	Trailer roof	NF	Poor	1-5%	3	400 LF 121.9 LM
19	Duct seam tape	Basement	F	Fair	10-15%	3	30 LF 9.1 LM
<b>TOTAL QUANTITY OF ACM</b>							<b>1,719 SF 400 LF</b>
<b>ESTIMATED ABATEMENT COST</b>							

<sup>1</sup> F = Friable; NF = Nonfriable      Friability is further defined in section 4.  
<sup>2</sup> Cond. = Condition Of Materials      Either good, fair or poor.  
<sup>3</sup> ND = None Detected  
 \* Point Count Analysis

**SECTION 1**  
 1.2 Survey Summary & Results

**ACM SURVEY RESULTS - Parcel No. 4ADD002**  
**Single Family Residence**  
**407 Placher Court**  
**Chillicothe, Illinois 61523**

The following homogeneous building material types were sampled as part of this survey and their results are summarized in the table below:

MTL #	MATERIAL DESCRIPTION	LOCATION	F/NF <sup>1</sup>	COND. <sup>2</sup>	% ACM <sup>3</sup>	# SAMPLES	QUANTITY (ENG/MET)
01	Drywall/joint compound	Throughout	NF	Good	1-5%	3	Approx. 2,500 SF 232.3 SM
02	Attic insulation	Attic	F	Fair	ND	3	900 SF 83.6 SM
03	1' x 1' white vinyl floor tile/mastic	Kitchen	NF	Good	ND/ND	3	175 SF 16.3 SM
04	12" x 12" brown vinyl floor tile/mastic	Kitchen, below group 3	NF	Poor	Tile 5-10% Mastic 1-5%	3	175 SF 16.3 SM
05	12" x 12" multi-color vinyl floor tile/mastic	Bathroom	NF	Good	ND/ND	3	40 SF 3.7 SM
06	12" x 12" light brown vinyl floor tile/mastic	Bathroom	NF	Poor	ND/ND	3	40 SF 3.7 SM
07	12" x 12" multi-color vinyl floor tile/mastic	Bedrooms, below hardwood flooring	NF	Poor	ND/ND	3	395 SF 36.7 SM
08	1' x 1' white glue-on ceiling tile/mastic	Basement hallway	NF	Good	Tile ND Mastic 1-5%	3	25 SF 2.3 SM
09	2' x 4' white lay-in ceiling	Basement	F	Good	ND	3	395 SF 36.7 SM
10	12" x 12" green/white floor tile/mastic	Basement laundry room	NF	Good	ND/ND	3	100 SF 9.3 SM
11	12" x 12" blue/white vinyl floor tile/mastic	Basement	NF	Good	ND/ND	3	180 SF 16.7 SM
12	12" x 12" brown vinyl floor tile/mastic	Basement, east room	NF	Good	Tile 1-5% Mastic ND	3	120 SF 11.1 SM
13	Multi-layer roofing shingles	House roof	NF	Good	ND	3	1,134 SF 105.3 SM
14	Roof shingles	Garage roof	NF	Good	ND	3	575 SF 53.4 SM
15	Roof shingles	Shed roof	NF	Good	ND	3	64 SF 5.9 SM
<b>TOTAL QUANTITY OF ACM</b>							<b>2,820 SF</b>
<b>ESTIMATED ABATEMENT COST</b>							

<sup>1</sup> F = Friable; NF = Nonfriable      Friability is further defined in section 4.  
<sup>2</sup> Cond. = Condition Of Materials      Either good, fair or poor.  
<sup>3</sup> ND = None Detected  
 \* Point Count Analysis