



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 7, 2016

SUBJECT: FAP 525 (Harrison Avenue)
Section 01-00509-00-RP (Rockford)
Winnebago County
Contract No. 85612
Item 1X
January 15, 2016 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 1 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.
Acting Bureau Chief of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

The following Special Provisions supplement the “Standard Specifications for Road and Bridge Construction”, Adopted January 1, 2012, the latest edition of the “Manual on Uniform Traffic Control Devices for Streets and Highways”, and the “Manual of Test Procedures of Materials” in effect on the date of invitation of bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included here in which apply to and govern the construction of Section 01-00509-00-RP, Rockford, and in case of conflict with any part, or parts, of said Specifications, the said Special Provisions shall take precedence and shall govern.

SPECIAL PROVISIONS

The following Special Provisions supplement the “Standard Specifications for Road and Bridge Construction”, adopted January 1, 2012, the latest edition of the “Manual on Uniform Traffic Control Devices for Streets and Highways” and the “Manual of Test Procedures for Materials” in effect on the date of the invitation for bids, and the “Supplemental Specifications and Recurring Special Provisions” indicated on the Check Sheet included herein which apply to and govern the construction of Harrison Avenue, F.A. Rte. 525, Section 01-00509-00-RP, in Winnebago County, City of Rockford and in case of conflict with any part, or parts, of said Specifications, the said Special Provisions shall take precedence and shall govern.

Where the term “Department” appears in the Specifications, the “City of Rockford” shall be substituted therefore, and where any term for an employee of the Department is used, the designated City of Rockford employee shall be substituted therefore. Where the term “Engineer” is used it shall mean the City of Rockford Engineer. The Standard Specifications for Water and Sewer Main Construction in Illinois, latest edition, and the City of Rockford Water Division Specifications – latest revision, and the General Provisions and Technical Specifications for Sanitary Sewer Construction in the Rock River Water Reclamation District shall also apply to this improvement where appropriate. Style, type and grade of applicable materials used for construction shall be in conformance with the City of Rockford Water Division Specifications (Chapter 12) – latest revision.

Herein after the terms “Owner”, “City” or “Engineer” shall mean the City of Rockford and its designated representatives and the term “Contractor” shall mean the entity that proposes to perform the work herein described or its designated subcontractors. The abbreviation RRWRD shall represent the Rock River Water Reclamation District.

Preliminary Site Investigation (PSI) Reports for the project are available for viewing at the City of Rockford website, located here: <http://rockfordil.gov/public-works/major-projects/harrison-avenue-corridor-reconstruction.aspx>.

LOCATION OF PROJECT

Harrison Avenue from the intersection of 9th Street and Harrison Avenue to approximately 550 feet east of the intersection of 20th Street and Harrison Avenue in Section 36, Twp 44 N. Range 1 E. of the 3rd P.M. Also, 11th Street from approximately 300 feet south of Alton Avenue to 700 feet north of Harrison Avenue

DESCRIPTION OF WORK

The work under this contract consists of the complete reconstruction of Harrison Avenue and 11th Street including new PCC pavement, curb and gutter, sidewalk, shared use path, box culvert replacement, box culvert extension, highway lighting, traffic signal replacement, and new storm sewer, sanitary replacement and adjustments, and water main replacement. From