



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 28, 2015

SUBJECT: FAI Route 72 (I-72)
Section D6 BRIDGE CLEANING 2016-2
Pike County
Contract No. 72I06
Item No. 115, January 15, 2016 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 2 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Roger Driskell, Region 4, District 6; Tim Kell; D. Carl Puzey; Estimates

CR/ck

Limitations of Construction: The Contractor shall coordinate the items of work in order to keep hazards and traffic inconveniences to a minimum, as specified below.

1. During the construction of this section, the following shall apply: At least one lane shall remain open to traffic at all times.
2. The Contractor shall provide, erect, and maintain all the necessary barricades, cones, drums, and lights for the warning and protection of traffic, as required by Sections 107 and 701 through 703 of the Standard Specifications, and as modified. The Contractor will be responsible for the traffic control devices at all times during construction activities and shall coordinate the items of work in order to keep hazard traffic inconveniences to a minimum.

All Advance warning signs shall be in new or like new condition at the start of the project. All warning signs shall be 48-inches by 48-inches and have a black legend on a fluorescent orange reflectorized background.

3. All post mounted signs shall use 100 x 100 mm (4x4 inches) wood posts according to Article 1007.05 of the Standard Specifications. The use of metal posts will not be permitted.
4. Work shall be accomplished using traffic control standards 701101, 701106, 701400 and 701406. No night time lane closures will be permitted. Traffic control detailed in standard 701406, will be paid for at the lump sum unit price for TRAFFIC CONTROL AND PROTECTION, STANDARD 701406. All other traffic control will not be measured for payment.

BRIDGE WASHING

Work shall be according to Section 592 of the Standard Specifications and as modified below.

The exterior areas of the structure to be washed shall be limited to the deck surface, both faces of parapets, deck drains, and expansion joints. Additionally, all debris within bridge abutment vaults shall be removed and disposed of.

The method of measurement and basis of payment shall be per Articles 592.06 and 592.07 respectively. For payment purposes, SN 075-0122 shall be defined as location #1, and SN 075-0123 shall be defined as location #2.