



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 7, 2016

SUBJECT: FAU 8891 (Springer Ave. / Sheridan Ave.)  
Section 12-00102-00-RS (Edwardsville)  
Madison County  
Contract No. 97605  
Item 125  
January 15, 2016 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised page 17 of the Special Provisions.**
- 2. Revised Index to Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.  
Acting Bureau Chief of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger, P.E.", with the initials "P.E." written in a smaller font to the right of the signature.

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

Saw-cutting, removing, and replacing the existing pavement shall be considered included in the cost of CURB REMOVAL, (SPECIAL).

### **CONTRACTOR ACCESS**

At road closure locations, where Type III barricades are installed in a manner that will not allow Contractor access to the project without relocation of one or more of the barricades, the arrangement of the barricades at the beginning of each work day may be relocated, when approved by the Engineer, in the manner shown on Highway Standard 701901. At the end of each work day, the barricades shall be moved and the road shall be closed to traffic.

The cost incurred by the Contractor in complying with this requirement shall be considered included in the contract unit prices bid for the various items of traffic control work involved and no additional compensation will be allowed.

### **KEEPING LANES OPEN TO TRAFFIC**

~~This work shall consist of furnishing, installing and maintaining required lighting, signing, or manpower to maintain traffic in a safe manner, as shown on the plans and as described herein.~~

~~All construction operations that require lane closures that would limit the two lane, two-way traffic to one lane, the Contractor shall conduct these operations between the hours of 7:00 pm and 6:00 am Sunday night through Friday morning.~~

~~The cost incurred by the Contractor in complying with this requirement shall be considered as included in the contract unit prices bid for the various traffic control items involved.~~

### **TRAFFIC CONTROL AND PROTECTION, (SPECIAL)**

This work shall consist of furnishing, installing, maintaining and removing all traffic control devices for traffic control and protection as shown on Highway Standards 701001, 701006, 701301, 701501, 701801, 701901, and BLR 22 included in the plans, according to the TRAFFIC CONTROL PLAN, according to Section 701 of the "Standard Specifications for Road and Bridge Construction", as directed by the Engineer and as specified herein.

Prior to beginning work on the project, the Contractor shall furnish and install Type III barricades and advance warning signs as detailed in the applicable Highway Standards. Barricade placement and sign spacing may be adjusted by the Engineer to suit field conditions.

**SPECIAL PROVISIONS**

**FAU ROUTE 8891 (SPRINGER/SHERIDAN AVENUE)  
SECTION: 12-00102-00-RS  
PROJECT: M-5011 (385)  
EDWARDSVILLE, ILLINOIS**

**INDEX TO SPECIAL PROVISIONS**

DESCRIPTION OF WORK .....	1
SHOP DRAWINGS .....	1
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT ....	2
SEQUENCE OF CONSTRUCTION OPERATIONS.....	2
TRAFFIC CONTROL PLAN .....	3
PUBLIC NOTICE.....	4
REMOVING LANDSCAPING FROM RIGHT-OF-WAY LIMITS .....	4
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.....	5
EARTH EXCAVATION.....	5
TOPSOIL FURNISH AND PLACE, 4" .....	5
SEEDING, CLASS 1, SPECIAL.....	6
INCIDENTAL HOT-MIX ASPHALT SURFACING .....	6
PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6".....	6
EXPANSION JOINTS .....	7
PORTLAND CEMENT CONCRETE SIDEWALK, THICKNESS SPECIFIED.....	7
DETECTABLE WARNINGS.....	8
HOT-MIX ASPHALT SURFACE REMOVAL.....	9
DRIVEWAY AND SIDEWALK REMOVAL .....	12
CLASS C PATCHES.....	12
WATER VALVES TO BE ADJUSTED.....	13
PIPE DRAINS, 4" .....	13
MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID.....	13
PROTECTION AND RESTORATION OF TRAFFIC SIGNS .....	14
TELESCOPING STEEL SIGN SUPPORT .....	14
CURB REMOVAL, (SPECIAL).....	16
CONTRACTOR ACCESS .....	17
<del>KEEPING LANES OPEN TO TRAFFIC.....</del>	<del>17</del>
TRAFFIC CONTROL AND PROTECTION, (SPECIAL).....	17
STATUS OF UTILITIES TO BE ADJUSTED.....	19
PAYROLLS and PROCEDURES .....	20