CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% Fed / 20% State	80% Fed / 20% State
				BRIDGE	BRIDGE
				0059	0059
				016-2512	016-2513
60604300	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (VARIABLE WIDTH GUTTER FLAG)	FOOT	369	184	185
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	151	75	76
60626300	STABILIZED MEDIAN SURFACE	SQ YD	4,024	2,012	2,012
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1,413	706	707
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	5	2	3
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	5	2	3
63200310	GUARDRAIL REMOVAL	FOOT	1,993	996	997
63800920	MODULAR GLARE SCREEN SYSTEM, TEMPORARY	FOOT	1,138	569	569
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	580	290	290
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	1	1
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1	0.5	0.5
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	0.5	0.5
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	4	2	2 △2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	6	6

* SPECIALTY ITEM

△2 REVISED SHEET 12/21/2020

REV-SEP

MODEL: Default
FILE NAME: pw:\\vksp-pw.bentley.com:exp-pw-04\Documents\Projects\D-91-055-19\800 CADD Design\801 Contracts\801-07 Civil\Sheet\D9105519-sht-Summary of Quantities-004

FILE NAME = D9105519-sht-Summary of Quantities-004	USER NAME = anthony.friedman	DESIGNED -	REVISED -
		DRAWN - AMF	REVISED -
GARZA KARHOFF ENGINEERING, LLC	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/14/2020	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
IL ROUTE 50 (CICERO AVENUE)
OVER BRC RAILROAD

SUMMARY OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	2018-124-BR	COOK	95	7
		CONTRACT NO. 62H50		
		ILLINOIS FED. AID PROJECT		