



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 8, 2021

SUBJECT: FAI Route 39 (I-39)  
Project NHPP-L8FB(633)  
Section (50-6HB-1)I-3  
LaSalle County  
Contract No. 66L00  
Item No. 27, January 15, 2021 Letting  
Addendum C

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions.
2. Revised page 97 of the Special Provisions.
3. Added page 163 to the Special Provisions.
4. Revised sheet 2 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

## TABLE OF CONTENTS

LOCATION OF PROJECT .....	1
DESCRIPTION OF PROJECT .....	1
PAVEMENT PATCHING .....	1
APPROACH SLAB REPAIR .....	4
BRIDGE DECK CONCRETE SEALER .....	10
BRIDGE DECK LATEX OR MICROSILICA CONCRETE OVERLAY, CUT OFF DATE .....	12
WIDTH RESTRICTION SIGN .....	12
VEHICLE PARKING .....	12
CHANGEABLE MESSAGE SIGN .....	12
PLASTIC DRUMS .....	13
TEMPORARY INFORMATION SIGNING .....	13
LINEAR DELINEATOR PANELS, 6 INCH .....	13
LINEAR DELINEATOR PANELS, 4 INCH .....	16
RESTORATION OF WORK AREA .....	18
CLEANING AND PAINTING EXISTING STEEL STRUCTURES .....	18
BRIDGE DECK LATEX CONCRETE OVERLAY .....	43
CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES .....	54
HOT-MIX ASPHALT SURFACE REMOVAL DECK .....	71
DECK SLAB REPAIR .....	71
STRUCTURAL REPAIR OF CONCRETE .....	77
PREFORMED BRIDGE JOINT SEAL .....	88
RESTORING BRIDGE APPROACH MEDIAN USING HIGH-DENSITY FOAM .....	95
STEEL BRIDGE RAIL POSTS .....	96
TRAFFIC CONTROL AND PROTECTION (SPECIAL) .....	97
WARRANTY FOR CLEANING AND PAINTING STEEL STRUCTURES .....	97
COMPENSABLE DELAY COSTS (BDE) .....	107
CONTRAST PREFORMED PLASTIC PAVEMENT MARKING (BDE) .....	111
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) .....	112
DISPOSAL FEES (BDE) .....	121
EMULSIFIED ASPHALTS (BDE) .....	122
ENGINEER'S FIELD OFFICE AND LABORATORY (BDE) .....	125
GROOVING FOR RECESSED PAVEMENT MARKINGS (BDE) .....	128
MOBILIZATION (BDE) .....	130
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE) .....	130

Revised 1/8/2021

PORTLAND CEMENT CONCRETE PAVEMENT PATCHING (BDE)..... 131  
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE) ..... 132  
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) ..... 142  
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) ..... 154  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 154  
TEMPORARY PAVEMENT MARKING (BDE)..... 155  
TRAFFIC CONTROL DEVICES - CONES (BDE)..... 158  
WARM MIX ASPHALT (BDE) ..... 158  
WEEKLY DBE TRUCKING REPORTS (BDE)..... 160  
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) ..... 160  
WORKING DAYS (BDE) ..... 162  
TEMPORARY RUMBLE STRIPS (SPECIAL)..... 163

Revised 1/8/2021

## **TRAFFIC CONTROL AND PROTECTION (SPECIAL)**

This work shall include furnishing, installing, maintaining, replacing, relocating and removing all traffic control devices used for the purpose of regulating, warning, or directing traffic along I-39, and adjacent entrance and exit ramps during Stage 1, and Stage 2. Traffic control and protection shall be provided as called for on the stage construction plan sheets, the Standard Specifications in accordance with Standard 701402, these special provisions, or as directed by the Engineer.

This work will be paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION (SPECIAL). This price shall be payment in full for all labor, materials, transportation, handling, and any other work necessary to furnish, install, maintain, replace, relocate and remove all traffic control devices required in the plans and specifications in accordance with the Standards 701402. Temporary concrete barrier, temporary pavement marking, and pavement marking removal shall be paid for separately as well as traffic control and protection pay items included in the plans.

## **WARRANTY FOR CLEANING AND PAINTING STEEL STRUCTURES**

Effective: March 3, 2000

Revised: November 24, 2004

Description. This work consists of providing a warranty for the cleaning and painting of existing steel structures as performed under the following pay items; CLEANING AND PAINTING STEEL BRIDGE and CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES, and/or CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES at the designated location(s).

The Contractor shall unconditionally warrant to the Illinois Department of Transportation (IDOT) that all work completed under the above contract pay items, including all materials and workmanship furnished by the Contractor and subcontractors, shall comply with the Contract, and that the cleaning and painting system applied to the bridge be free of defects, as hereinafter defined for a period of two years after the Warranty Period Start Date.

Revised 12/21/2020  
Revised 1/8/2021

**TEMPORARY RUMBLE STRIPS (SPECIAL)**

Description. This work shall consist of the furnishing, installation, maintenance, and removal of temporary rumble strips and advance signage.

Materials. Materials shall be according to the following.

Item	Article/Section
(a) Sign Posts, Metal (Note 1) .....	1093.01(a)
(b) Sign Posts, Wood (Note 2) .....	1007.05
(c) Preformed Plastic Pavement Markings.....	780.07

Note 1. Galvanizing of metal posts will not be required.

Note 2. The nominal size of wood posts shall be 4 x 4 in. (100 x 100 mm).

Equipment. Equipment shall be according to the following.

Item	Article/Section
(a) Signs .....	1106.01

**CONSTRUCTION REQUIREMENTS**

General. The rumble strips shall consist of multiple layers of Preformed Plastic Pavement Marking, Type B - Inlaid - Line 6" (White). The multiple layers shall be placed as to maintain a 1/2" thickness over the length of the strip. The temporary rumble strips shall be placed as shown on the Traffic Control and Protection, Plan Details or as directed by the Engineer.

Advance Signage. In advance of the temporary rumble strips, advance signage shall be furnished and installed as shown on the Traffic Control and Protection, Plan Details

Method of Measurement. This work will be measured for payment as each, where each is defined as a set of three temporary rumble strips across a single lane of pavement; and each set of temporary rumble strips will be measured for payment once.

Furnishing, installation and removal of the advance signage shall not be paid for separately but shall be included in the cost of the "Temporary Rumble Strip (Special) item.

Basis of Payment. This work will be paid for at the contract unit price per each for TEMPORARY RUMBLE STRIPS (SPECIAL) which price shall include all materials and labor to complete this work.

Added 1/7/2021