

CODE No.	ITEM	UNIT	COUNTY: WHITE	
			ROUTE: FAP 332 (IL 1)	FUNDING: 80% FED / 20% STATE
			LOCATION: RURAL	
			TOTAL QUANTITY	S.N. 097-2018 CTC - 0010
28100207	STONE RIPRAP, CLASS A4	TON	68	68
28100209	STONE RIPRAP, CLASS A5	TON	390	390
28200200	FILTER FABRIC	SQ YD	806	806
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	568	568
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	60	60
42000060	WELDED WIRE REINFORCEMENT	SQ YD	182	182
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	182	182
44000100	PAVEMENT REMOVAL	SQ YD	133	133
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	474	474
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	195	195
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	31630	31630
50800515	BAR SPLICERS	EACH	176	176
50900200	STEEL RAILING, TYPE 2399	FOOT	64	64
51500100	NAME PLATES	EACH	1	1

2

1

REV. 1-5-2021

REV. 12-16-2020

MODEL: D:\cadd\... FILE NAME: S:\CADD\_Drawing\CAD\_Drawing\767 - Henderson\767-172E (R) Rte 1 over Lick Creek\CADD\_Sheets\09086510e-Summary.dgn



USER NAME = jbeque	DESIGNED - J.E.B.	REVISED -
PLOT SCALE = 40.0000' / in.	DRAWN - J.E.B.	REVISED -
PLOT DATE = 9/29/2020	CHECKED - R.H.D.	REVISED -
	DATE - 09/29/2020	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
ILLINOIS ROUTE 1 OVER LICK CREEK

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	2B-3	WHITE	45	5
CONTRACT NO. 78328				
ILLINOIS FED. AID PROJECT				

COUNTY:	WHITE
ROUTE:	FAP 332 (IL 1)
FUNDING:	80% FED / 20% STATE
LOCATION:	RURAL
TOTAL QUANTITY	S.N. 097-2018 CTC - 0010

CODE No.	ITEM	UNIT	TOTAL QUANTITY	
52200010	TEMPORARY SHEET PILING	SQ FT	751	751
54003000	CONCRETE BOX CULVERTS	CU YD	193.1	193.1
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	136	136
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	125	125
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	916	916
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15	15
67100100	MOBILIZATION	L SUM	1	1
<del>70100100</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701316</del>	<del>EACH</del>	<del>1</del>	<del>1</del>
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1

\* SPECIALTY ITEM

△ REV. 1-5-2021

MODEL: D:\cadd\... FILE NAME: S:\CADD Drawings\CAD Drawings\767 - Henderson\767-172E (R) Rte 1 over Lick Creek\CADD Sheets\09086510e-Summary.dgn



USER NAME = jbeque	DESIGNED - J.E.B.	REVISED -
PLOT SCALE = 40.0000 ' / in.	DRAWN - J.E.B.	REVISED -
PLOT DATE = 9/29/2020	CHECKED - R.H.D.	REVISED -
	DATE - 09/29/2020	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
ILLINOIS ROUTE 1 OVER LICK CREEK

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	2B-3	WHITE	45	6
			CONTRACT NO. 78328	
		ILLINOIS	FED. AID PROJECT	