



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 4, 2021

SUBJECT FAU Route 2711 (IL 131)
Project STP-FZ5X(647)
Section 2020-129-RS&SW
Lake County
Contract No. 62M07
Item No. 94, January 15, 2021 Letting
Addendum C

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 144 to the Special Provisions.
4. Revised sheet 6 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION (ROADWAY GRINDING,
 RESURFACING, & PATCHING OPERATIONS) 58
 PEDESTRIAN PUSH-BUTTON 62
 REBUILD EXISTING HANDHOLE..... 63
 RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON..... 63
 BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) 64
 COMPENSABLE DELAY COSTS (BDE)..... 65
 CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)..... 69
 DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 71
 DISPOSAL FEES (BDE) 80
 EMULSIFIED ASPHALTS (BDE) 81
 ENGINEER’S FIELD OFFICE AND LABORATORY (BDE) 84
 FUEL COST ADJUSTMENT (BDE)..... 87
 HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE) 90
 HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (MODIFIED FOR I-FIT)
 (D-1) 93
 HOT MIX ASPHALT - PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS -JOBSITE
 SAMPLING (BDE) 97
 MOBILIZATION (BDE) 102
 PORTLAND CEMENT CONCRETE – HAUL TIME (BDE)..... 102
 RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE) 103
 REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) 113
 SILT FENCE, INLET FILTERS, GROUND STABILIZATION AND RIPRAP FILTER FABRIC (BDE)..... 124
 SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 130
 SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 131
 TEMPORARY PAVEMENT MARKING (BDE)..... 131
 TRAFFIC CONTROL DEVICES - CONES (BDE)..... 134
 TRAINING SPECIAL PROVISIONS (BDE) 134
 IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION..... 137
 WARM MIX ASPHALT (BDE) 139
 WEEKLY DBE TRUCKING REPORTS (BDE)..... 141
 WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 141
 WORKING DAYS (BDE) 143
 MODIFY EXISTING CONTROLLER CABINET 144

MODIFY EXISTING CONTROLLER CABINET

Effective: May 22, 2002

Revised: July 1, 2015

895.01TS

The work shall consist of modifying an existing controller cabinet as follows:

- (a) Uninterruptable Power Supply (UPS). The addition of uninterruptable power supply (UPS) to an existing controller cabinet could require the relocation of the existing controller cabinet items to allow for the installation of the uninterruptable power supply (UPS) components inside the existing controller cabinet as outlined under Sections 862 and 1074.04 of the Standard Specifications and the wiring of UPS alarms.
- (b) Light Emitting Diode (LED) Signal Heads, Light Emitting Diode (LED) Optically Programmed Signal Heads and Light Emitting Diode (LED) Pedestrian Signal Heads. The contractor shall verify that the existing load switches meet the requirements of Section 1074.03(b)(2) of the Standard Specifications and the recommended load requirements of the light emitting diode (LED) signal heads that are being installed at the existing traffic signal. If any of the existing load switches do not meet these requirements, they shall be replaced, as directed by the Engineer.
- (c) Light Emitting Diode (LED), Signal Head, Retrofit. The contractor shall verify that the existing load switches meet the requirements of Section 1074.03(b)(2) of the Standard Specifications and the recommended load requirements of light emitting diode (LED) traffic signal modules, pedestrian signal modules, and pedestrian countdown signal modules as specified in the plans. If any of the existing load switches do not meet these requirements, they shall be replaced, as directed by the Engineer.
- (d) This item shall include the upgrade of all non-railroad controller software to the latest version available at the time of the signal TURN-ON.

Basis of Payment.

Modifying an existing controller cabinet will be paid for at the contract unit price per each for MODIFY EXISTING CONTROLLER CABINET. This shall include all material and labor required to complete the work as described above, the removal and disposal of all items removed from the controller cabinet, as directed by the Engineer. The equipment for the Uninterruptable Power Supply (UPS) and labor to install it in the existing controller cabinet shall be included in the pay item Uninterruptable Power Supply, Special or Uninterruptable Power Supply, Ground Mounted.

Added 1/4/2021