

PAYCODE	ITEM DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
20200100	EARTH EXCAVATION	CU YD	640	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	534	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	105	
25000210	SEEDING, CLASS 2A	ACRE	0.1	
28000510	INLET FILTERS	EACH	4	
28100107	STONE RIPRAP, CLASS A4	SQ YD	340	
28200200	FILTER FABRIC	SQ YD	355	
* 30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	1,370	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	2,185	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1,370	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	4,380	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	880	
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SQ YD	1,370	
42000070	PAVEMENT CONNECTOR (HMA) FOR BRIDGE APPROACH SLAB	SQ YD	118	
42001300	PROTECTIVE COAT	SQ YD	970	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	738	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	660	
44000100	PAVEMENT REMOVAL	SQ YD	2,001	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	533	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	582	
44000600	SIDEWALK REMOVAL	SQ FT	2,608	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	
50200100	STRUCTURE EXCAVATION	CU YD	370	
50300225	CONCRETE STRUCTURES	CU YD	88.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	218.5	
50300260	BRIDGE DECK GROOVING	SQ YD	646	
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	115.8	
50401325	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BEAMS, IL45N	FOOT	553.5	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	107,070	
Δ 50900105	ALUMINUM RAILING, TYPE L	FOOT	170	
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	562	
51202305	DRIVING PILES	FOOT	562	
51203200	TEST PILE METAL SHELLS	EACH	1	
51204650	PILE SHOES	EACH	12	
51500100	NAME PLATES	EACH	1	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1	
54248510	CONCRETE COLLAR	CU YD	0.7	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	151	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	58	
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	34	

PAYCODE	ITEM DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
55100500	STORM SEWER REMOVAL 12"	FOOT	85	
55100700	STORM SEWER REMOVAL 15"	FOOT	33	
55100900	STORM SEWER REMOVAL 18"	FOOT	16	
55101100	STORM SEWER REMOVAL 21"	FOOT	15	
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2	
58600101	GRANULAR BACKFILL FOR STRUCTURES	CU YD	145	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	80	
60108204	PIPE UNDERDRAINS, TYPE 2, 4"	FOOT	42	
X6024242	INLET, SPECIAL NO. 1	EACH	4	
60200305	CATCH BASINS, TYPE A, 4"-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	
Δ 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	53	
60500040	REMOVING MANHOLES	EACH	4	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	678	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1,010	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1	
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	LSUM	1	
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	15	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	
67100100	MOBILIZATION	L SUM	1	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	200	
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,800	
X0322463	CONNECTION TO EXISTING SEWER	EACH	1	
* X0326806	WASHOUT BASIN	L SUM	1	
* X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	100	
* X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5	
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	
* Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	
* Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	204	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	
* Z0076600	TRAINEES	HOUR		1,000
* Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR		1,000

HRG PROJECT NO.: 80709
 HRG PROJ. CONTACT:
 FILE NAME: 80709.dwg
 PLOT FILE: 80709.dwg
 PEN TABLE: pen.tbl



USER NAME = whoad	DESIGNED - JCH	REVISED - 12/16/2020 JRM Δ
PLOT SCALE =	DRAWN - CL	REVISED -
PLOT DATE = 12/16/2020	CHECKED - JRM	REVISED -
	DATE - 10/19/2020	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SEMINARY STREET
 SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION NO.	COUNTY	TOTAL SHEETS	SHEET NO.
5112	19-00630-00-BR	WINNEBAGO	41	3
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 85703	

* SPECIAL PROVISION
 Δ SPECIALTY ITEM