



# Illinois Department of Transportation

Office of Intermodal Project Implementation / Division of Aeronautics  
1 Langhorne Bond Drive / Springfield, Illinois 62707-8415

January 4, 2021

SUBJECT: Litchfield Municipal Airport (3LF)  
Litchfield, Illinois  
Montgomery County  
Illinois Project Number: 3LF-4819  
SBG Project Number: 3-17-SBGP-144/156/162  
Contract No. LI039  
Item No. 01A, January 15, 2021 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

Reason for Addendum:  
Earthwork Clarification

To All Plan Holders:  
Per bidder request, see attached spreadsheet of cross-sectional end areas (sq ft.) for proposed Taxiways B and B3.

Plan Changes:  
No Changes

Special Provisions Changes:  
No Changes

Schedule of Prices Changes:  
No Changes

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Questions on this addendum may be directed to Kyle Schweizer, P.E. of Hanson Professional Services Inc. at 217.747.9219.

<b>3LF-4819 CROSS SECTION END AREAS</b>				
<b>TWY B</b>	<b>STATION</b>	<b>CUT (SF)</b>	<b>FILL-PAVE (SF)</b>	<b>FILL-GEN. (SF)</b>
to 50' LT	99+50	0.00	0.00	0.00
to 50' LT	100+18	42.30	53.90	16.05
to 50' LT	100+50	40.15	56.75	15.25
	101+00	28.65	29.25	34.10
	101+50	43.55	23.80	29.70
	102+00	21.10	16.55	26.75
	102+50	25.35	10.90	17.75
	103+00	35.80	0.00	4.60
	103+50	40.70	0.00	3.20
	104+00	58.70	0.00	8.00
	104+50	61.65	0.00	13.40
	105+00	79.20	0.00	13.55
	105+50	90.45	0.00	16.15
	106+00	93.90	1.05	18.65
	106+50	88.35	1.20	17.65
	107+00	70.65	5.60	10.90
	107+50	63.35	2.90	17.80
	108+00	66.45	1.55	16.25
	108+50	78.80	0.00	16.55
	109+00	86.60	0.00	15.35
	109+50	88.30	0.00	16.75
	110+00	80.75	0.00	16.60
	110+50	73.95	0.00	18.45
	111+00	66.70	1.05	20.75
	111+50	65.85	1.15	19.80
	112+00	62.80	0.00	19.15
	112+50	54.30	0.00	22.60
	113+00	47.90	0.00	24.90
	113+50	72.45	0.00	6.40
	114+00	30.35	0.00	11.95
	114+50	25.00	0.00	8.50
	115+00	18.55	0.00	14.50
	115+50	27.40	0.00	8.60
	115+79	100.45	0.00	0.00
<b>TWY B3</b>	<b>STATION</b>	<b>CUT (SF)</b>	<b>FILL-PAVE (SF)</b>	<b>FILL-GEN. (SF)</b>
	0+50	36.50	63.50	68.55
	1+00	36.60	65.75	78.05
	1+50	40.40	70.25	94.60
	2+00	20.00	84.00	112.85
	2+50	20.95	3.20	14.90
	3+00	14.45	0.00	14.90
	3+50	20.55	0.00	32.10
	3+63	0.00	0.00	65.15