			CONTRACT NO.		
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	2005-0331		37	37	
STA.		TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT			
60A04					

ROAD WORK

AHEAD

EXPECT DELAYS

68 (1700)

54 (1350)

7 (175) 7 (175)

①

45 (1125)

7 (175) 7 (175) 5 (125) 5 (125) 7 (175) 7 (175) 5 (125) 5 (125) 7 (175) 7 (175)

7' (2.1 m) MIN.

1 (25) BLACK BORDER

USE APPROPRIATE MONTH AND DATE FOR CONTRACT

②

11 (275)

BEGINS XXX XX

58 (1450)

NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
R. MIRS	9-15-97	ARTERIAL ROAD
R. MIRS	12-11-97	INFORMATION SIGN
T. RAMMACHER	2-2-99	
C. JUCIUS	1-31-07	
		SCALE: NONE
		DRAWN BY DESIGN
		CHECKED BY
		TC22