*REF-
*REF-
*REF-

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
876	9Y-RS-7	WILL	100	42
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 60E52

1. PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.
WITH GRATING FOR CONC. FES, 600 mm
STA. 1+267.775, 9.48m RT
INV. 231.089

2. CB, 1.5m, TY A, W/ TY8 GRATE
STA. 1+279.60, 9.542 RT
T.G. 232.189
INV. 231.140 (N)
INV. 231.150 (S)

3. CB, 1.5m, TY A, W/ TY8 GRATE
STA. 1+296.54, 9.592 RT
T.G. 232.360
INV. 231.198 (N)
INV. 231.220 (S)

4. PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.
WITH GRATING FOR CONC. FES, 375 mm
STA. 1+267.775, 9.48m LT
INV. *

5. CB, 1.5m, TY A, W/ TY8 GRATE
STA. 1+316.694, 9.410 RT
T.G. 232.576
INV. 231.274 (N)
INV. 231.533 (S)

6. PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.
WITH GRATING FOR CONC. FES, 375 mm
STA. 1+332.500, 9.302m LT
INV. *

7. CB, 1.2m, TY A, W/ TY8 GRATE
STA. 1+359.840, 9.302 RT
T.G. 233.125
INV. 231.743 (N)
INV. 231.749 (S)

8. CB, 1.2m, TY A, W/ TY8 GRATE
STA. 1+396.830, 9.112 RT
T.G. 233.000
INV. 231.857 (N)
INV. 231.761 (S)

9. CB, 1.2m, TY A, W/ TY8 GRATE
STA. 1+436.526, 8.955 RT
T.G. 233.445
INV. 232.046 (N)
INV. 232.052 (S)

10. CB, 1.2m, TY A, W/ TY8 GRATE
STA. 1+459.557, 9.105 RT
T.G. 233.430
INV. 232.172 (N)
INV. 232.171 (S)

11. CB, 1.2m, TY A, W/ TY8 GRATE
STA. 1+482.711, 10.625 RT
T.G. 233.275
INV. 232.298 (N)
INV. 232.402 (S)

12. PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.
WITH GRATING FOR CONC. FES, 375 mm
STA. 1+489.714, 9.302m RT
INV. *

13. PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.
WITH GRATING FOR CONC. FES, 600 mm
STA. 1+732.540, 13.738m LT
INV. 230.581

14. PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.
WITH GRATING FOR CONC. FES, 600 mm
STA. 1+736.730, 12.480m RT
INV. 230.401

15. PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.
WITH GRATING FOR CONC. FES, 375 mm
STA. 1+730.604, 9.483m LT
INV. 232.000

16. PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.
WITH GRATING FOR CONC. FES, 375 mm
STA. 1+742.240, 25.314m LT
INV. 230.450

17. PRECAST REIN. CONC. FLARED END SECTION, 450 mm DIA.
WITH GRATING FOR CONC. FES, 450 mm
STA. 1+798.632, 9.060m RT
INV. 229.961

18. PRECAST REIN. CONC. FLARED END SECTION, 450 mm DIA.
WITH GRATING FOR CONC. FES, 450 mm
STA. 1+799.182, 8.960m LT
INV. 230.101

19. PRECAST REIN. CONC. FLARED END SECTION, 450 mm DIA.
WITH GRATING FOR CONC. FES, 450 mm
STA. 1+859.700, 8.108m LT
INV. 231.691

20. PRECAST REIN. CONC. FLARED END SECTION, 450 mm DIA.
WITH GRATING FOR CONC. FES, 450 mm
STA. 1+878.330, 8.117m LT
INV. 231.759

21. PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.
WITH GRATING FOR CONC. FES, 600 mm
STA. 1+997.940, 9.000m RT
INV. 228.639

22. PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.
WITH GRATING FOR CONC. FES, 600 mm
STA. 2+008.230, 9.000m RT
INV. 228.379

23. PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.
WITH GRATING FOR CONC. FES, 375 mm
STA. 2+056.180, 8.992m LT
INV. 226.732

24. PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.
WITH GRATING FOR CONC. FES, 375 mm
STA. 2+066.332, 8.993m LT
INV. 226.585

25. PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.
WITH GRATING FOR CONC. FES, 375 mm
STA. 2+450
INV. 221.453

26. CB, 1.5 m, TY A, W/ TY8 GRATE
STA. 2+500
INV. 220.075 (N)
INV. 219.875 (S)

27. PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.
WITH GRATING FOR CONC. FES, 375 mm
STA. 2+542
INV. 218.497

* TO BE DETERMINED
IN THE FIELD BY THE ENGINEER

1 Rev. Sheet 1-6-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

IL. ROUTE 1
DRAINAGE STRUCTURE TABLE

SCALE: NONE DRAWN BY HMO
DATE: 9/5/2008 CHECKED BY R.K.

12-31-08-R1

9/5/2008
c:\projects\d136602\typicals.dgn
wilgreendp