

S.P.	ITEM NO.	ITEMS	UNIT	URBAN 80% FED. 20% STATE				
				QUANTITY	ROADWAY 1000-2A	BRIDGE X0 71-2A	CULVERT X0 28-2A	LANDSCAPING Y007
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1092	1092			
	44000300	CURB REMOVAL	FOOT	357	357			
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	700	700			
*	44004300	PAVEMENT BREAKING	SQ YD	4064	4064			
*	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	295	295			
	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	720	720			
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	4539	4539			
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
	50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1			1	
*	50105220	PIPE CULVERT REMOVAL	FOOT	442	442			
	50200100	STRUCTURE EXCAVATION	CU YD	1296		467	829	
	50300225	CONCRETE STRUCTURES	CU YD	146.9		146.9	0	
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	409.2		409.2	0	
	50300260	BRIDGE DECK GROOVING	SQ YD	1213		1213	0	
	50300280	CONCRETE ENCASEMENT	CU YD	24.8		24.8	0	
	50500305	ERECTING STRUCTURAL STEEL	L SUM	1		1	0	
	50500505	STUD SHEAR CONNECTORS	EACH	8112		8112	0	
	50800105	REINFORCEMENT BARS	POUND	134960		0	134960	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	103930		103930	0	
	50800515	BAR SPLICERS	EACH	90		90	0	
	51200957	FURNISHING METAL SHELL PILES 12" x 0.250"	FOOT	1386		1386	0	
	51201600	FURNISHING STEEL PILES HP12X53	FOOT	1375		1375	0	
	51202305	DRIVING PILES	FOOT	2761		2761	0	
	51203200	TEST PILE METAL SHELLS	EACH	2		2	0	
	51203600	TEST PILE STEEL HP12X53	EACH	2		2	0	
	51204650	PILE SHOES	EACH	54		54	0	
	51500100	NAME PLATES	EACH	3		1	2	
	52100520	ANCHOR BOLTS, 1"	EACH	64		64	0	
	54003000	CONCRETE BOX CULVERTS	CU YD	578.3		0	578.3	
	54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	50	50			
	54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	573	573			
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2			
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	16	16			
	54215547	METAL END SECTIONS 12"	EACH	2	2			
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	27	27			
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	67		67	0	

FILE NAME =
#FILE#

USER NAME = #USER#
PLOT SCALE = NONE
PLOT DATE = 10/10/2008

DESIGNED - GJM
DRAWN - GJM
CHECKED - EJM
DATE - 3/11/2008

REVISED - 5/13/2008
REVISED - 7/18/2008
REVISED - 9/30/2008
REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES
SCALE: NONE SHEET NO. 2 OF 4 SHEETS STA. 59+00 TO STA. 89+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
324	23B-1	MCHENRY	97	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				