

**PROPOSED PAVING SCHEDULE**

LOCATION	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 13"	AGGREGATE SUBGRADE 12"	COMB CONC C&G TY B-6.24	GUTTER OUTLET	HOT-MIX ASPHALT SHLD 8"	HOT-MIX ASPHALT SHLD 6"	AGGREGATE SHLD TYPE B 6"	BITUMINOUS MATERIALS (PRIME COAT)	BRIDGE APPROACH PAVEMENT
	TON	SQ YD	FOOT	EACH	SQ YD	SQ YD	SQ YD	GAL	SQ YD
IL ROUTE 23									
Sta. 59+00.00 to Sta. 59+80.00	223	277	142.0						22
Sta. 59+80.00 to Sta. 67+42.50	2033	3464	665.7	2	907	153			203
Sta. 70+62.50 to Sta. 88+20.00	4686	9812			3594	567	267		469
Sta. 88+20.00 to Sta. 89+00.00	221	164			37		28		22
<b>Totals</b>	<b>7165</b>	<b>13718</b>	<b>808</b>	<b>2</b>	<b>4539</b>	<b>720</b>	<b>295</b>		<b>717</b>

**ROADWAY REMOVAL SCHEDULE**

LOCATION	PAVEMENT REMOVAL	PAVEMENT BREAKING	COMB C & G REMOVAL	CURB REMOVAL	DRIVEWAY PVMT REMOVAL	STEEL PLATE BEAM GUARDRAIL REMOVAL, ATTACHED TO STRUCTURE	GUARDRAIL REMOVAL	TERMINAL SECTION REMOVAL AND SALVAGE	PIPE CULVERT REMOVAL
	SQ YD	SQ YD	FOOT	FOOT	SQ YD	FOOT	FOOT	EACH	FEET
IL ROUTE 23									
Sta. 59+00.00 to Sta. 67+72.50	2544		699	133	295		204	2	188
Sta. 67+72.50 to Sta. 84+50.00		4063		67	337	742		2	103
Sta. 84+50.00 to Sta. 89+00.00	1309			157	460				151
<b>Totals</b>	<b>3853</b>	<b>4064</b>	<b>700</b>	<b>357</b>	<b>1092</b>	<b>742</b>	<b>204</b>	<b>4</b>	<b>442</b>

**PAVEMENT MARKING SCHEDULE**

LOCATION	THERMOPLASTIC PAVEMENT MARKING LINE						POLYUREA PAVEMENT MARKING TYPE I LINE							
	4"		6"		12"		4"		6"		12"		24"	
	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	WHITE	WHITE
	FOOT		FOOT		FOOT		FOOT		FOOT		FOOT		FOOT	
IL ROUTE 23														
STA 59+00 TO STA 67+42.50	1685	1685												
STA 67+42.50 TO STA 70+62.50							640	640						
STA 70+62.50 TO STA 89+00	3675	3675												
<b>SUBTOTALS</b>	<b>5360</b>	<b>5360</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>640</b>	<b>640</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>
<b>TOTALS</b>		<b>10720</b>	<b>0</b>		<b>0</b>	<b>0</b>		<b>1280</b>	<b>0</b>		<b>0</b>		<b>0</b>	<b>0</b>

FILE NAME =	USER NAME = #USER#	DESIGNED - GJM	REVISED - 5/13/2008	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#		DRAWN - GJM	REVISED - 7/18/2008					324	23B-1	MCHENRY	97	11
PLOT SCALE = #SCALE#		CHECKED - EJL	REVISED - ---		SCALE: NONE	SHEET NO. 2 OF 5 SHEETS	STA. 59+00 TO STA. 89+00	CONTRACT NO. 62892				
PLOT DATE = 9/30/2008		DATE - 3/11/2008	REVISED - ---		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							