

LANDSCAPING AND EROSION CONTROL SCHEDULE

LOCATION	TOPSOIL FURNISH AND PLACE, 6"	SEEDING, CLASS 4	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	NITROGEN FERTILIZER	PHOSPHORUS FERTILIZER	POTASSIUM FERTILIZER	EROSION CONTROL BLANKET	EARTH EXCAVATION FOR EROSION CONTROL	TEMPORARY EROSION CONTROL SEEDING	FILTER FABRIC	STONE RIPRAP CLASS A3
	SQ YD	ACRE	EACH	FOOT	POUNDS	POUNDS	POUNDS	SQ YD	CU YD	ACRE	SQ YD	SQ YD
IL ROUTE 23												
Sta. 59+00.00 LT to Sta. 59+90.71 LT	143	0.03		100.80	2.7	2.7	2.7	143		0.03		
Sta. 59+00.00 RT to Sta. 59+94.08 RT	146	0.03		105.88	2.7	2.7	2.7	146		0.03		
Sta. 60+19.11 LT to Sta. 63+20.34 LT	795	0.16		321.33	14.8	14.8	14.8	795		0.16		
Sta. 60+23.68 RT to Sta. 62+05.87 RT	291	0.06		185.63	5.4	5.4	5.4	291		0.06		
Sta. 62+30.43 RT to Sta. 67+92.48 RT	1675	0.35		589.09	31.1	31.1	31.1	1675		0.35		
Sta. 63+35.54 LT to Sta. 68+03.83 LT	1357	0.28		492.40	25.2	25.2	25.2	1357		0.28		
Sta. 68+55.42 RT to Sta. 83+38.86 RT	4348	0.90		389.99	80.9	80.9	80.9	4348		0.90		
Sta. 68+63.20 LT to Sta. 73+36.22 LT	1810	0.37		1346.90	33.7	33.7	33.7	1810		0.37		
Sta. 73+60.22 LT to Sta. 84+17.73 LT	3253	0.67		1158.63	60.5	60.5	60.5	3253		0.67		
Sta. 83+56.98 RT to Sta. 84+20.43 RT	160	0.03		63.45	3.0	3.0	3.0	160		0.03		
Sta. 84+55.43 RT to Sta. 85+05.54 RT	126	0.03		391.96	2.3	2.3	2.3	126		0.03		
Sta. 84+58.27 LT to Sta. 87+97.61 LT	435	0.09		50.11	8.1	8.1	8.1	435		0.09		
Sta. 85+40.54 RT to Sta. 89+00.00 RT	523	0.11		374.46	9.7	9.7	9.7	523		0.11		
Sta. 88+27.64 LT to Sta. 89+00.00 LT	104	0.02		46.59	1.9	1.9	1.9	104		0.02		
Sta. 59+00.00 LT to Sta. 67+00.00 LT			5						66.7		6.7	6.7
Sta. 59+00.00 RT to Sta. 67+00.00 RT			7						155.6		6.7	6.7
Sta. 73+00.00 RT to Sta. 89+00.00 RT			7						111.1		0	0
Sta. 73+00.00 LT to Sta. 89+00.00 LT			11						355.6		0	0
Totals	15167	3.13	30	5618	283	283	283	15167	689	3.13	14	14

GUARDRAIL SCHEDULE

STATION	GUARDRAIL TYPE A FOOT	GUARDRAIL ATTACHED TO STRUCTURE FOOT	TBT TYPE 1, SPECIAL (TANGENT) EACH	TBT TYPE 2 EACH	TBT TYPE 6 EACH	GUARDRAIL MARKER TYPE A EACH	TERMINAL MARKER - DIRECT APPLIED EACH
IL ROUTE 23							
STA 65+99.85 TO STA 67+41.85 (RT)	175						3
STA 66+29.35 TO STA 67+41.85 (LT)	112.5						2
STA 70+63.15 TO STA 73+13.15 (LT)	250						4
STA 70+63.15 TO STA 77+38.15 (RT)	675						5
STA 73+48.20 TO STA 77+35.70 (LT)	387.5						5
STA 77+35.70 TO 77+85.70 (LT)		50					
STA 77+38.15 TO 77+88.15 (RT)		50					
STA 77+85.70 TO 79+85.70 (LT)	200						3
STA 77+87.50 TO 79+25 (RT)	137.5						2
STA 65+16.85 (RT)				1			1
STA 65+79.35 (LT)				1			1
STA 80+35.70 (RT)				1			1
STA 73+16.22 (CURVED)					1		1
STA 73+80.22 (CURVED)					1		1
STA 79+75 (LT)				1			1
STA 67+72.50 (RT)					1		
STA 67+72.50 (LT)					1		
STA 70+32.50 (RT)					1		
STA 70+32.50 (LT)					1		
TOTALS	1937.5	100	4	2	4		24

FILE NAME =	USER NAME = *USER*	DESIGNED - GJM	REVISED - 7/18/2008	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILEL	PLOT SCALE = *SCALE*	DRAWN - GJM	REVISED - 9/30/2008					324	23B-1	MCHENRY	97	13
	PLOT DATE = 9/30/2008	CHECKED - EJL	REVISED - ---		SCALE: NONE	SHEET NO. 4 OF 5 SHEETS	STA. 59+00 TO STA. 89+00	CONTRACT NO. 62892				
		DATE - 3/11/2008	REVISED - ---					FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				