

HEUER AND ASSOCIATES

Consulting Engineers

2315 Enterprise Drive - Suite 102 Westchester, IL 60154-5811 708-492-1000

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
1004	08-00079-01-FP	COOK	46	6
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CONTRACT No. 63007

SCHEDULE OF QUANTITIES - ROADWAY REMOVAL

STATION	40600982	44001900	44004400	44004700	XX005314	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL, SPECIAL
	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	PAVEMENT REMOVAL (SPECIAL)	SIDEWALK REMOVAL, SPECIAL	BITUMINOUS DRIVEWAY REMOVAL	
	SQ YD	FOOT	SQ YD	SQ FT	SQ YD	
29+81.33 TO 34+00	40	808	1,213	4,909	33	106
34+00 TO 39+60	62	1,125	1,846	4,859	54	120
39+60 TO 45+53.65	162	1,246	2,017	1,541	117	94
TOTAL	264	3,179	5,076	11,309	204	320 *

* To be measured and paid for as Pavement Removal (Special). See PCC Driveway Removal Special Provision.

SCHEDULE OF QUANTITIES - BITUMINOUS PAVEMENT

STATION	21001000	31101000	40600100	40600300	40701921	HOT-MIX ASPHALT SURFACE COURSE - BUTT JOINT
	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SUB-BASE GRANULAR MATERIAL, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 12"	
	SQ YD	TON	GALLON	TON	SQ YD	
29+81.33 TO 34+00	1,416	368	554	2	1,231	40
34+00 TO 39+60	2,094	545	819	4	1,821	62
39+60 TO 45+53.65	2,276	592	891	4	1,979	162
TOTAL	5,786	1,505	2,264	10	5,031	264

SCHEDULE OF QUANTITIES - ALLEYS AND DRIVEWAYS

STATION	42300300	XX001109	CLASS C PATCH (CONCRETE)	CLASS D PATCH (ASPHALT)
	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	PORTLAND CEMENT CONCRETE ALLEY PAVEMENT, 8"		
	SQ YD	SQ YD		
29+81.33 TO 34+00	134	0	1	11
34+00 TO 39+60	177	21	16	14
39+60 TO 45+53.65	135	21	7	33
TOTAL	446	42	24	58

SCHEDULE OF QUANTITIES - SIDEWALKS AND CURBS

STATION	42400200	60600605	60604400	XX007729
	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	CONCRETE CURB, TYPE B	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	DETECTABLE WARNING, SPECIAL
	SQ FT	FOOT	FOOT	SQ FT
29+81.33 TO 34+00	4,528	0	818	8
34+00 TO 39+60	4,837	0	1,133	88
39+60 TO 45+53.65	1,398	140	1,230	64
TOTAL	10,763	140	3,181	160

EARTH EXCAVATION

STATION	20200100
	UNSUITABLE EXCAVATION
	CU YD
29+81.33 TO 34+00	245
34+00 TO 39+60	206
39+60 TO 45+53.65	435
TOTAL	886

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**BLUFF AVENUE IMPROVEMENTS
STAGE 1**

SCHEDULE OF QUANTITIES

SCALE:
DATE 08/28/2008

DRAWN BY H&A
CHECKED BY PFH

PLAN	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
NO.	REGISTERED	
	BY	
	DATE	
	FILE NAME	

PROFILE	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
NO.	REGISTERED	
	BY	
	DATE	
	FILE NAME	